

RIGID FRAME BRIDGE DESIGN

A THESIS

Submitted for the Degree of
MASTER OF SCIENCE IN CIVIL ENGINEERING
Georgia School of Technology


By

Henry G. Palmer

B. S. in C. E. 1930

THE UNIVERSITY OF GEORGIA

Approved by:



SPECIAL COMMITTEE ON APPROVAL.

Date: _____

32012


INTRODUCTION

INTRODUCTION

One of the newest and most important developments in the construction of short span bridges is the introduction of the rigid frame principle to their design. This principle has been used for a number of years in other construction but only recently has it been applied to the design of bridges.

Much credit is due to Mr. Arthur G. Hayden, Designing Engineer of the Westchester County Park Commission, New York, and his staff of assistants for their fine work toward developing this theory. Other engineers have contributed greatly toward advance on the subject but Mr. Hayden, by both design and actual construction, has proven beyond a doubt the economy and safety of this type of bridge. The Westchester County Park Commission has constructed many rigid frame bridges of reinforced concrete and structural steel on its magnificent system of parkways and aside from their other advantages, the ease with which the esthetic phases may be developed stands out as a very favorable point.

A glance at the general shape of the rigid frame bridge will suffice to show how admirably it answers all of the requirements for a crossing over an intersecting highway or railroad. It is probably better suited to be used as this type of bridge than any other, although as a crossing over a stream it has the advantage of offering the maximum area of waterway passage for a given length of bridge. Too, the length of span possible is much higher for the rigid frame type of bridge than for the simple slab and girder type and the longer spans are often very highly desirable.



*Steel Rigid Frame Bridge.
Westchester County Park System.*



*Reinforced Concrete Rigid Frame Bridge.
Stone facing helps give this structure a very
pleasing appearance.*

The design of bridges of this type is based on sound engineering principles and should not be thought of as a mere experiment. The structure, however, is highly indeterminate and the conditions of stress set up in some portions are very complicated. A number of tests have been made in an effort to clarify these conditions but as yet the available data is somewhat meager. The possibilities in the field of experimentation are still great.

Laboratory analyses in attempts to determine the action of the frame under load have been very successful and have contributed greatly to establish confidence in the theoretical approaches used. These tests have been made on small, flat models of some elastic substance, such as celluloid or pasteboard. These models, because of their homogeneity, can be relied upon to yield theoretically correct results which can be applied to actual structures with relatively small error. Further discussion of this method of analysis will be made later.

Bridges of composite materials such as reinforced concrete cannot be expected to act exactly as a more homogeneous body but the inaccuracies in the design assumptions are not sufficient to materially affect the safety of the design. The writer has constructed a reinforced concrete model of a typical rigid frame bridge and by strain gauge measurements under load has gathered some data by which he hopes to prove that the actual stresses developed substantially corroborate those expected from the design.

THEORY OF THE DESIGN

THEORY OF THE DESIGN

From an engineering standpoint the design of a structure is essentially a study of the economics of the situation. This statement must not be construed to mean that all other consideration should be disregarded entirely, because in innumerable cases, the engineer must vary his design greatly to meet architectural and other requirements. It can readily be seen, however, that after determining the essential duties that the structure should be expected to perform, the next step must be to decide in what way all of its functions might be developed with the least possible annual expense. By annual expense is meant not only the initial investment, but also a number of other factors which are very important. Of course, the life of the structure is a most essential consideration as this makes a very great difference in the annual cost. Maintenance, salvage value of materials, interest on investment and insurance premiums must also be considered. The architectural requirements must be weighed against these factors and the design carried out in an effort to give all points their proper consideration.

The rigid frame bridge is adaptable to structural steel and to reinforced concrete. In this paper no effort will be made to compare the relative merits of the two types as this comparison must necessarily be made with reference to a specific case. The essentials of the design are practically the same for bridges of both materials so we may consider the principles involved in the design of one of reinforced concrete and the same general methods could be applied to one of steel.

In the selection of a bridge type, especially for a crossing over an intersecting railroad, street or highway, an important factor to consider is the approach fills at the ends of the bridge. Although not true in every case, the approaches can usually be constructed more economically if the grade is as low as possible. The limiting factor is in most cases the clearance required under the bridge. By using a rigid frame bridge the required clearance can be obtained with very economical approaches. This is true because of the small crown depth of the structure and because the top of the slab can be given a shape to conform to a rising approach from both sides. These advantages are also realized by a flat arch, but the arch must have a much higher rise than the frame type. Because of the greater rise ratio the arch cannot have the same clearance at the haunches as it has at the crown, nor can it keep the same low grade if the clearance at the haunches is increased. Too, the heavy abutments required by the arch are very expensive and their cost is enough to make the rigid frame much more economical.

When a structure is placed under load it is a well known fact that a deflection is caused and enough work is performed by the structure in supporting the load to exactly equal the product of the load times half of the distance it moves. From this principle the basic economy of the rigid frame can be seen at once. The bridge is so proportioned and built that the deflection of the load is much smaller than it would be on a girder and slab type and hence, the internal work performed is less. Too, the material in the frame can be so efficiently distributed that each portion does some of the work required and no parts are idle.

Also, the deflections produced are such that the fills at the ends of the bridge can be used to help perform the required work, by resisting the deflection at the ends of the structure. All of these design factors combine to make the rigid frame bridge a most economical type and one that is rapidly gaining favor among bridge designers.

The rigid frame bridge is, in all cases, a statically indeterminate structure. The degree of indeterminacy, however, is variable depending on the number of spans and the conditions of the footings. Of course, those of more than one span are highly indeterminate and the mathematical analysis is long and arduous. It has been found by experience that laboratory analyses on elastic models is more practical and can be carried out so much more easily that this method has found preference over the strictly mathematical approach in the case of the multiple span frames. Therefore, no attempt will be made in this paper to present the theoretical design of the more indeterminate cases.

In the single span design two different cases must be considered, each of which requires an entirely different method of approach. The first is when the footings of the bridge rest free upon the foundation material and no bending moment at the footing can be assumed. The other case is when the footings can be so keyed or anchored into the foundation material that a condition of fixity can be assumed. Of course, in many cases some fixity can be secured by the use of foundation piles or other such means, and this would necessarily affect

the design. But even though the two types are designed from a different standpoint, the closeness of the results, makes it very easy to take care of both cases with very little loss in economy.

The free end bridge is indeterminate to the first degree since we have two unknown horizontal reaction components and two unknown vertical components with only three static equations with which to solve them. The fixed end bridge is indeterminate to the third degree since, in addition to the unknowns in the other case, it has two unknown moments which makes it have six unknowns in all and only three equations.

The missing equations which are required in order to be able to solve for the unknowns must be provided from a study of the laws of flexure. Let us first consider any small segment of a beam subjected to flexure, as represented by Fig. 1. The length of the segment is s and its original position before bending is shown by the dotted lines.




Fig. 1

After bending the segment would take a shape like that shown in heavy lines (of course, greatly exaggerated). The fiber at a distance c from the neutral axis will have elongated by an amount $c\Delta\theta$. But from the fact that the modulus of elasticity is equal to the stress divided by the strain, we can say that this elongation is equal to the stress in the fiber times the length of the fiber

divided by E or $\frac{sp}{E}$, when p is equal to the stress in the fiber. Now $p = \frac{Mc}{I}$, M being bending moment on the section, so elongation becomes $\frac{Mcs}{EI}$. Equating, $c\Delta\theta = \frac{Mcs}{EI}$ or $\Delta\theta = \frac{Ms}{EI}$. This same thing is true of all small segments in a beam so the total change in angle between the tangents at the ends of the beam is the sum of all these small changes or $\sum \frac{Ms}{EI}$.

If the beam were curved before the bending moment was applied, the small segment would appear as shown in Fig. 2. θ is the angle between the tangents before bending and θ' is the angle after bending.




Fig. 2.

If s is the length of the segment at the neutral axis, $s/c\theta$ is the length of a fiber at a distance c from the neutral axis. After flexure the length of the same fiber is $s/c\theta'$. The change of length is $(s/c\theta') - (s/c\theta) = c\Delta\theta$. Assuming again a moment M on the section and a fiber stress of $\frac{Mc}{I}$, we have a change in length of the fiber equal to $\frac{Mc(s/c\theta)}{EI}$.

Letting $c\Delta\theta = \frac{Mc(s/c\theta)}{EI}$ or $\frac{Mc}{I} = \frac{c\Delta\theta}{s/c\theta} E = f$. If we consider

this fiber to have a cross-section area of a then its moment about the neutral axis is equal to $facs$ or $\frac{ac^2\Delta\theta E}{s/c\theta}$. The resisting moment of

the section being the summation of the moments of all the fibers then $M = \frac{ac^2 \Delta\theta E}{s/c\theta}$. But the sum of all the infinitesimal cross-sections times the squares of their distances from the neutral axis is the moment of inertia of the section so we can substitute I for ac^2 in the above expression. It then becomes $M = \frac{IE \Delta\theta}{s/c\theta}$. Solving for $\Delta\theta$, we obtain: $\Delta\theta = \frac{M(s/c\theta)}{IE}$, which might be written also:

$\Delta\theta = \frac{Ms}{IE}$ since $s/c\theta$ is practically equal to s for ordinary curvatures in rigid frame or arch ribs. As before, the total change in angle between the tangents at the ends of the axis, θ , is equal to $\sum \frac{Ms}{EI}$.

A rigid frame bridge with free end conditions is, from a design standpoint, similar to a curved beam as shown in Fig. 3.




Fig. 3.

Let us first consider that the left end is restrained from lateral movement and the right end is on rollers. Then when the small division s of the axis is subjected to an external bending moment, M , causing a flexure, the angular change between the tangents at its ends, $\Delta\theta$, is equal to $\frac{Ms}{EI}$. This angular change times the height of the segment, y , is the horizontal displacement of the free end of the beam. The magnitude of this movement is, therefore, equal to $\frac{y Ms}{EI}$. From all such segments on the axis of the beam the displacement must be equal to $\sum \frac{y Ms}{EI}$. But both ends of the actual beam are restrained from moving and a horizontal force must be acting on the end to cause an equal and opposite displacement to that caused by the externally applied moment. The moment in any segment from this horizontal force is equal to Hy . Then the displacement caused by the horizontal reaction is, as before, $\sum \frac{(Hy)sy}{EI}$ or $\sum \frac{Hy^2 s}{EI}$. These two displacements being equal and opposite:

$$\sum \frac{Mys}{EI} - \sum \frac{Hy^2 s}{EI} = 0$$

$$\text{or } H = \frac{\sum \frac{Mys}{EI}}{\sum \frac{y^2 s}{EI}}$$

$$\text{If } E \text{ is constant, } H = \frac{\sum \frac{Mys}{I}}{\sum \frac{y^2 s}{I}}$$

Now if we so choose our axis divisions that all divisions s are equal, then the equation is further simplified, so that:

$$H = \frac{\sum \frac{My}{I}}{\sum \frac{y^2}{I}}$$

Since the free end frame was indeterminate to only the first degree, this equation gives us all the necessary ones to solve for the reactions and also for the internal stresses after the reactions are found. However, there are other conditions affecting the stresses in the structure. The earth pressure from the fills at the ends of the bridge is very important. This is dealt with as if it were an external load so no further design complications are caused.

Sometimes a change in span length is caused by other factors than a horizontal reaction. Referring again to the equation previously

derived:-
$$H = \frac{\sum \frac{Mys}{EI}}{\sum \frac{y^2s}{EI}}$$

we can notice that the numerator of the right hand side is the expression for total horizontal displacement of the curved beam before the horizontal reaction was applied. If we call this horizontal displacement Δl ,

we can let
$$\Delta l = \sum \frac{Mys}{EI} = H \sum \frac{y^2s}{EI} \quad \text{or}$$

$$\Delta l = \frac{H}{E} \sum \frac{y^2s}{EI}$$

$$H = \frac{E \Delta l}{\sum \frac{y^2s}{EI}}$$

The last form is an expression for the horizontal reaction due to any change of span length Δl .

A change of span length may be caused by a rise or fall in temperature. From the laws of thermal expansion we know that Δl would be equal to $c \Delta t l$; c being the coefficient of temperature, Δt being the rise or fall of temperature in degrees, and l being span length.

From our general equation for H we may write

$$H = \frac{E_c t l}{s \sum \frac{y^2}{I}}$$

A rise in temperature is used with a positive sign and a fall with a negative sign, thereby making the results agree with the assumed sign convention; that is, a positive H resists spreading of the footings, a negative H resists a movement toward each other.

Rib shortening is another cause of tendency to change span length. It has an effect similar to a fall in temperature. All thru the rib there is a thrust acting with a normal component N . Letting f_c represent the compression due to N in pounds per square unit on any segment of the rib, we can express the shortening of the segment as $\frac{f_c s}{E}$. Then the shortening of the whole arch is $\sum \frac{f_c s}{E}$. But to find Δl we must express this as horizontal displacement, which we can easily do, since the horizontal projection of s is Δx .

$$\therefore \text{we may write } \Delta l = \sum \frac{f_c \Delta x}{E}$$

Substituting this value for Δl into the general equation for change in span length we have $H = \frac{f_c \Delta x}{\sum \frac{y^2}{I}}$.

But since s may be assumed constant we have $H = \frac{f_c \Delta x}{\sum \frac{y^2}{I}}$

With the above equations we are able to carry thru the design of the free end rigid frame, taking into consideration all of the points which affect the design from a practical standpoint.

Next we shall consider the case of the structure with con-

ditions causing restraint at the footings. This structure is indeterminate to the third degree so we must supply three equations from the laws of flexure to supplement the three statical equations which we already have. To do this we may turn to the case of a curved cantilever beam as shown in Fig. 4.




Fig. 4.

If a flexure $\Delta\theta$ is caused in a small segment of length s of the beam, a displacement is caused at the free end. Assuming the origin of coordinates to be at the free end we can express the components of this movement. The horizontal displacement is $y\Delta\theta$ and the vertical displacement is $x\Delta\theta$. $\Delta\theta$ is equal to $\frac{Ms}{EI}$, as shown before, so the components of movement due to the flexure in the small segment are $\frac{Mys}{EI}$ and $\frac{Mxs}{EI}$. The total horizontal displacement is $\sum \frac{Mys}{EI}$, the total vertical displacement is $\sum \frac{Mxs}{EI}$, and the total angular change between the ends is $\sum \frac{Ms}{EI}$.

The rigid frame bridge with fixed end conditions is similar to that shown in Fig. 5.




Fig. 5.

As will be seen later the derivation of the equations for this case includes several terms from which $\sum \frac{ys}{EI}$ may be factored. For this reason we can choose our origin of coordinates so as to make this factor equal to 0. By making Z of such a value that the XX axis passes thru the center of gravity of the quantities $\frac{s}{I}$, this will be made true and the labor of calculation will be shortened.

By assuming that the bridge is made up of two curved cantilever beams as shown, we can apply the principles of the preceding paragraph. A load p is assumed on each half, which cause a moment on the left half of M_L and one on the right half of M_R . The unknown reactions due to the loads are assumed to be applied at the origin of coordinates, and connected to the ends of the beams by an imaginary rigid arm. The deflections caused by the various moments in the beams can be calculated

for each half and we know that the two sides will necessarily still coincide. Therefore, we know that the angular change in each cantilever is numerically the same but with opposite signs with relation to the two halves. Likewise the vertical deflections must be equal and with the same sign, and the horizontal deflections are equal but with opposite signs, since one side is elongated and the other one shortened.

The different flexure producing, agencies are, on the left cantilever, M_1 , M_0 , V and H . On the right cantilever, they are M_r , M_0 , V and H .

If we equate the horizontal deflections in the two halves we have:-

$$\sum M_1 \frac{ys}{EI} + M_0 \sum \frac{ys}{EI} + H_0 \sum \frac{y^2 s}{EI} + V_0 \sum \frac{xy s}{EI} \\ = - \left[\sum M_r \frac{ys}{EI} + M_0 \sum \frac{ys}{EI} + H_0 \sum \frac{y^2 s}{EI} - V_0 \sum \frac{xy s}{EI} \right]$$

This reduces to

$$- 2 H_0 \sum \frac{y^2 s}{EI} = \sum M_r \frac{ys}{EI} + \sum M_1 \frac{ys}{EI}$$

If we cancel the constant E from both sides and also make s constant we may write $- 2 H_0 \sum \frac{y^2}{I} = \sum M_r \frac{y}{I} + \sum M_1 \frac{y}{I}$

We can call $M_r + M_1 = M$, which further reduces the equation to:

$$- 2 H_0 \sum \frac{y^2}{I} = \sum M \frac{y}{I}$$

$$\text{or } H_0 = \frac{- \sum M \frac{y}{I}}{2 \sum \frac{y^2}{I}}$$

In the same way we can express the vertical deflections as:

$$\sum M_1 \frac{xs}{EI} + M_0 \sum \frac{xs}{EI} + H_0 \sum \frac{xy s}{EI} + V_0 \sum \frac{x^2 s}{EI}$$

$$= \left[\sum M_r \frac{xs}{EI} + M_o \sum \frac{xs}{EI} + H_o \sum \frac{xy s}{EI} - v_o \sum \frac{x^2 s}{EI} \right]$$

This reduces to:

$$\sum M_l \frac{xs}{EI} - \sum M_r \frac{xs}{EI} = -2 v_o \sum \frac{x^2 s}{EI}$$

Taking out E and s as before,

$$\begin{aligned} \sum M_l \frac{x}{I} - \sum M_r \frac{x}{I} &= -2 v_o \sum \frac{x^2}{I} \\ \text{or } v_o &= \frac{\sum M_r \frac{x}{I} - \sum M_l \frac{x}{I}}{2 \sum \frac{x^2}{I}} \end{aligned}$$

The angular change in the ends of the frame can be expressed as follows:

$$\begin{aligned} \sum M_l \frac{s}{EI} + M_o \sum \frac{s}{EI} + H_o \sum \frac{ys}{EI} + v_o \sum \frac{xs}{EI} \\ = - \left[\sum M_r \frac{s}{EI} + M_o \sum \frac{s}{EI} + H_o \sum \frac{ys}{EI} - v_o \sum \frac{xs}{EI} \right] \end{aligned}$$

This may be reduced to:

$$\begin{aligned} \sum M_r \frac{s}{EI} + \sum M_l \frac{s}{EI} &= -2 M_o \sum \frac{s}{EI} \\ \text{or } \sum \frac{M}{I} &= -2 M_o \sum \frac{1}{I} \\ \text{Solving for } M_o &= - \frac{\sum \frac{M}{I}}{2 \sum \frac{1}{I}} \end{aligned}$$

It must be noticed that all summations are for the half arch except those containing M , which must be for the whole arch since they are the combination of similar terms containing M_l and M_r .

With these three additional equations we have all that are required to solve for the unknown reactions due to external loads. As before, we can treat the pressure from the fills as any other external

load and solve without additional equations.

A change of span length due to some other agency than loads on a structure will cause direct tension or compression and therefore no angular change or vertical reaction. The right hand member of the equation $-2 H_o \sum \frac{y^2 s}{EI} = \sum M_r \frac{ys}{EI} + \sum M_l \frac{ys}{EI}$ is an expression for change in span length Δl , due to any cause whatever. Then:

$$\Delta l = -2 H_o \sum \frac{y^2 s}{EI}$$

$$\text{or } H_o = \frac{E \Delta l}{2 \sum \frac{y^2 s}{I}} \quad \text{or} \quad H_o = \frac{E \Delta l}{2 s \sum \frac{y^2}{I}}$$

For stretching of the arch, Δl is used with a positive sign and with a negative sign for compressing.

A rise or fall in temperature would cause a change in span length and consequently a horizontal reaction as shown above. Δl would be equal to ctl as in the case of the free end frame. If we substitute ctl for Δl in the general equation for change in span length, we obtain:

$$H_o = - \frac{Ectl}{2s \sum \frac{y^2}{I}}$$

For this case we must use t as positive for a fall in temperature, since this produces a stretching effect, and negative for a rise in temperature. This is not in accordance with the accepted sign conventions, so if desired we can write the equation,

$H_o = + \frac{Ectl}{2s \sum \frac{y^2}{I}}$ and we can use our regular signs for rise and fall in temperature.

Referring back to our calculations for rib shortening in the

case of the free end frame we can see that, $\Delta l = \sum \frac{f_c \Delta x}{E}$.

Substituting this into the general form of the equation for H_0 , we

$$\text{have } H_0 = -\frac{\sum f_c \Delta x}{\sum \frac{y^2}{I}}$$

Since rib shortening results in a stretching effect f_c is used with a positive sign, giving us a negative value for H_0 , that is, acting in the opposite direction from that shown in Fig. 5.

The unsymmetrical frame bridge offers very little additional complications since the theory is exactly the same as for the symmetrical structure. Either one of two expedients may be used and the same results obtained. The horizontal thrust can be assumed to act along




Fig. 6.




Fig. 7

the XX axis as shown in Fig. 6, and the moments due to it will be equal to P_y , with y measured perpendicular to the XX axis. The thrusts for the second case can be assumed to act horizontally and y measured in a vertical direction to the XX axis. In both cases the bending moments, M are calculated as if the structure were symmetrical. Care should be taken to carry all summations out for the full arch instead of the half arch as in the case of the symmetrical span.

PRACTICAL APPLICATION OF DESIGN

PRACTICAL APPLICATION OF DESIGN

From experience the rigid frame bridge has been found economical for span lengths of from 35 ft. to 80 ft. for reinforced concrete and from 80 ft. to 120 ft. for steel. As yet, however, experience has not determined any rigid limits of economy and comparisons must still be resorted to in order to determine the advisability of this type for a specific structure.

The design of a reinforced concrete bridge with free end conditions is carried thru in this paper and an attempt is made to show the application of the design principles as would be required in practice. The structure has been assumed to rest free upon the soil with the resultant earth pressure acting near the center of the base. The sketch of the half frame is shown in Fig. 8.

The structure chosen to illustrate the design has a span length of 81 ft. The lengths of the divisions s were made 3 ft., starting at the center of the span. This makes the divisions at the bottoms of the vertical legs of a different length but the values derived for them may be weighted in proportion to their length and correct results will be obtained. As a matter of fact, however, these bottom divisions have very little influence on the rest of the arch, and ignoring them makes little difference in the results. It can be noticed that a center of division point occurs at the bend in the knee. The divisions should be so made that this condition will prevail since this is the point of maximum negative moment and the stress conditions at this point should be obtained. The structure has such a flat curve that the horizontal projections of the divisions

s can also be assumed as 3 ft., and this saves us some labor in the calculations.

For convenience in calculations the origin of coordinates is assumed at the bottom of one of the legs at the imaginary hinge joint. The reactions are first assumed to act as in Fig. 8. Upon calculation, if they come out positive they will act in that direction, and if negative, in the opposite direction. All moments, due to either external loads or to reaction components, are tabulated positive if they conform to the regular sign convention for positive moments; i. e., producing compression on the outside fibers of the arch.

The procedure in the design is to assume first a general shape of the arch ring and reinforcing throughout. Then the moments of inertia can be computed and the frame constants determined.

Then by using influence loads at each center of division we can compute the moments at all points on the span by using our equations previously mentioned. The labor of working out the effects of these influence loads can be shortened by assuming a load greater than unity and of such a value that the smallest simple beam moment that must be dealt with is equal to 1. In the case under discussion the influence load used was 9 and this gave us a moment at Pt. 10₁ due to a load at 10₇ of:

$$1/27 \times 9 \times 3 = 1$$


Of course, the influence curves must be plotted to such a scale that we can read off 1/9 of the calculated values and get the influence curves for moment and thrust for a unit load.

After the influence lines have been constructed the work of finding the moments due to dead and live loads and also the normal thrusts is very easily accomplished. Then the same things are computed for the earth pressure, temperature stresses and rib shortening using the formulas already derived. The maximum positive and negative moments with their corresponding normal thrusts are then tabulated and the calculations for reinforcing at each section are carried thru. These calculations are made using the formulas for combined bending and direct stress. Much labor can be saved by using the table which is included in Hool and Johnson's Concrete Engineer's Handbook.

Some corrections may be necessary in the assumed sections in order to keep an economical design or to keep the stresses within the safe working limits. Sometimes compression reinforcement at the crown is economical in order to keep the crown depth low or to keep from over reinforcing for tension. Variations in assumed moments of inertia might vary as much as 20 per cent without seriously affecting the safety of the design. However, large variations in the moments of inertia should call for a recalculation.

Following is the complete set of calculations for the symmetrical rigid frame bridge with hinged conditions at the footings. It will be noticed in the design, Fig. 9, that stirrups are used in the rib of the arch. These stirrups are serving not as calculated shear reinforcing, but to support the extrados steel and to furnish an additional factor of safety in carrying the shear. Also, nominal rein-

forcing is used in the inside or soffit face of the vertical legs, although none is required from the calculations. Transverse tie rods are also used to prevent formation of cracks due to unequal settlement and other causes.



PRELIMINARY SKETCH
HALF SECTION
Showing Assumed Proportions.

FIGURE 8.

GA. SCHOOL OF TECHNOLOGY

SECTION OF
RIGID FRAME BRIDGE

Scale: 1" = 4'0"

June 1932

Point	t Feet	I_c $\frac{1}{12} t^3$	A_s Sq. Ft.	D $\frac{t}{2} - .17$	I_s $10 A_s D^2$	I $I_c + I_s$	Y	$\frac{Y^2}{I}$
1	2.0	60.75	0.0070	4.33	1.31	62.06	1.0	0.02
2	3.67	4.12	0.0140	1.67	0.39	4.51	4.0	3.55
3	4.00	5.33	0.0140	1.83	0.47	5.80	7.0	8.45
4	4.33	6.76	0.0140	2.00	0.56	7.32	10.0	13.66
5	4.69	8.60	0.0245	2.18	1.16	9.76	13.0	17.32
6	5.02	10.52	0.0245	2.34	1.34	11.86	16.0	21.59
7	5.35	12.75	0.0245	2.51	1.54	14.29	19.0	25.26
8	5.69	15.34	0.0245	2.68	1.76	17.10	22.0	28.50
9	6.00	18.00	0.0245	2.83	1.96	19.96	25.0	31.31
10	5.33	12.61	0.0245	2.50	1.53	14.14	25.87	47.33
11	4.75	8.93	0.0176	2.21	0.86	9.79	26.16	69.89
12	4.21	6.21	0.0176	1.94	0.66	6.87	26.42	101.60
13	3.75	4.39	0.0176	1.71	0.51	4.90	26.65	144.94
14	3.37	3.19	0.0217	1.52	0.50	3.69	26.84	195.20
15	3.08	2.44	0.0217	1.37	0.41	2.85	26.98	255.40
16	2.83	1.89	0.0217	1.25	0.34	2.23	27.10	333.81
17	2.58	1.43	0.0217	1.12	0.27	1.70	27.22	435.84
18	2.42	1.18	0.0326	1.04	0.35	1.53	27.30	487.12
19	2.25	.95	0.0326	0.96	0.30	1.25	27.38	599.68
20	2.08	.75	0.0326	0.87	0.25	1.00	27.46	754.05
21	2.00	.67	0.0326	0.83	0.22	0.89	27.50	849.72
22	2.00	.67	0.0326	0.83	0.22	0.89	27.50	849.72

$$\sum \frac{Y^2}{I} = 5273.76 \text{ for half span}$$

10,547.52 for full span

LOAD = 9

:Point :	I :	y :	Influence Load at 10 L				:Point:
:	:	:	Mom. :	My :	:	Total :	:
:	:	:	:	I :	Hy :	M :	:
: 1L	62.06	1.0	0	0	- .48	- .48	1L :
: 2L	4.51	4.0	0	0	1.92	1.92	2L :
: 3L	5.80	7.0	0	0	3.36	3.36	3L :
: 4L	7.32	10.0	0	0	4.80	4.80	4L :
: 5L	9.76	13.0	0	0	6.24	6.24	5L :
: 6L	11.86	16.0	0	0	7.68	7.68	6L :
: 7L	14.29	19.0	0	0	9.12	9.12	7L :
: 8L	17.10	22.0	0	0	10.56	10.56	8L :
: 9L	19.96	25.0	0	0	12.00	12.00	9L :
: 10L	14.14	25.87	26	47.57	13.58	13.58	10L :
: 11L	9.79	26.16	25	66.80	12.44	12.44	11L :
: 12L	6.87	26.42	24	92.30	11.32	11.32	12L :
: 13L	4.90	26.65	23	125.09	10.21	10.21	13L :
: 14L	3.69	26.84	22	160.02	9.12	9.12	14L :
: 15L	2.85	26.98	21	198.76	8.05	8.05	15L :
: 16L	2.23	27.10	20	243.05	6.99	6.99	16L :
: 17L	1.70	27.22	19	304.22	5.93	5.93	17L :
: 18L	1.53	27.30	18	321.16	4.90	4.90	18L :
: 19L	1.25	27.38	17	372.37	3.86	3.86	19L :
: 20L	1.00	27.46	16	439.36	2.82	2.82	20L :
: 21L	0.89	27.50	15	463.48	1.80	1.80	21L :
: 22L	0.89	27.50	14	432.58	.80	.80	22L :
: 22R	0.89	27.50	13	401.68	-.20	-.20	22R :
: 21R	0.89	27.50	12	370.79	-1.20	-1.20	21R :
: 20R	1.00	27.46	11	302.06	2.18	2.18	20R :
: 19R	1.25	27.38	10	219.04	3.14	3.14	19R :
: 18R	1.53	27.30	9	160.58	4.10	4.10	18R :
: 17R	1.70	27.22	8	128.10	5.07	- 5.07	17R :
: 16R	2.23	27.10	7	85.07	6.01	6.01	16R :
: 15R	2.85	26.98	6	56.80	6.95	6.95	15R :
: 14R	3.69	26.84	5	36.37	7.88	7.88	14R :
: 13R	4.90	26.65	4	21.75	8.79	8.79	13R :
: 12R	6.87	26.42	3	11.54	9.68	9.68	12R :
: 11R	9.79	26.16	2	5.34	10.56	10.56	11R :
: 10R	14.14	25.87	1	1.83	11.42	11.42	10R :
: 9R	19.96	25.0	0	0	12.00	12.00	9R :
: 8R	17.10	22.0	0	0	10.56	10.56	8R :
: 7R	14.29	19.0	0	0	9.12	9.12	7R :
: 6R	11.86	16.0	0	0	7.68	7.68	6R :
: 5R	9.76	13.0	0	0	6.24	6.24	5R :
: 4R	7.32	10.0	0	0	4.80	4.80	4R :
: 3R	5.80	7.0	0	0	3.36	3.36	3R :
: 2R	4.51	4.0	0	0	1.92	1.92	2R :
: 1R	62.06	1.0	0	0	- .48	- .48	1R :

$$\Sigma = 5067.71$$

$$H = \frac{\sum \frac{My}{I}}{\sum \frac{y^2}{I}} = \frac{5067.71}{10,547.52}$$

$$H = .48$$

Load = 9

Influence Load at 11L				
Point	Mom.	My I	Hy	Total M
1L	0	0	- .96	- .96
2L	0	0	3.84	3.84
3L	0	0	6.72	6.72
4L	0	0	9.60	9.60
5L	0	0	12.48	12.48
6L	0	0	15.36	15.36
7L	0	0	18.24	18.24
8L	0	0	21.12	21.12
9L	0	0	24.00	24.00
10L	25	45.73	24.85	74.58
11L	50	133.61	25.10	158.71
12L	48	184.60	25.40	210.00
13L	46	250.18	25.60	275.78
14L	44	320.04	25.79	345.83
15L	42	397.52	25.90	423.42
16L	40	486.10	26.02	512.12
17L	38	608.44	26.18	634.62
18L	36	642.38	26.21	668.59
19L	34	744.74	26.25	771.00
20L	32	878.72	26.36	905.08
21L	30	926.96	26.40	953.36
22L	28	865.16	26.40	891.56
22R	26	803.36	26.40	829.76
21R	24	741.58	26.40	767.98
20R	22	604.12	26.36	630.48
19R	20	438.08	26.25	464.33
18R	18	321.16	26.21	347.37
17R	16	256.20	26.18	282.38
16R	14	170.14	26.02	196.16
15R	12	113.60	25.90	139.50
14R	10	72.74	25.79	98.53
13R	8	43.50	25.60	69.10
12R	6	23.08	25.40	48.48
11R	4	10.68	26.10	36.78
10R	2	3.66	24.85	28.51
9R	0	0	24.00	24.00
8R	0	0	21.12	21.12
7R	0	0	18.24	18.24
6R	0	0	15.36	15.36
5R	0	0	12.48	12.48
4R	0	0	9.60	9.60
3R	0	0	6.72	6.72
2R	0	0	3.84	3.84
1R	0	0	- .96	- .96

= 10086.02

$$H = \frac{My}{I} = \frac{10,086.02}{10,547.52}$$

H = .96

Load = 9

Influence Load at 12L				
Point:	Mom.	$\frac{My}{I}$	H_y	Total
				M
1L	0	0	-1.43	-1.43
2L	0	0	5.72	5.72
3L	0	0	10.01	10.01
4L	0	0	14.30	14.30
5L	0	0	18.59	18.59
6L	0	0	22.88	22.88
7L	0	0	27.17	27.17
8L	0	0	31.46	31.46
9L	0	0	35.75	35.75
10L	24	43.92	37.99	-13.99
11L	48	128.26	37.41	10.59
12L	72	276.91	37.78	34.22
13L	69	375.29	38.11	30.89
14L	66	480.08	38.38	27.62
15L	63	596.42	38.58	24.42
16L	60	729.12	38.75	21.25
17L	57	912.68	38.92	18.08
18L	54	963.52	39.04	14.96
19L	51	1117.10	39.15	11.85
20L	48	1318.08	39.27	8.73
21L	45	1390.45	39.33	5.67
22L	42	1297.78	39.33	2.67
22R	39	1205.06	39.33	-.33
21R	36	1112.36	39.33	3.33
20R	33	906.18	39.27	6.27
19R	30	657.12	39.15	9.15
18R	27	481.76	39.04	12.04
17R	24	384.29	38.92	14.92
16R	21	255.19	38.75	17.75
15R	18	170.41	38.58	20.58
14R	15	109.10	38.38	23.38
13R	12	65.27	38.11	26.11
12R	9	34.61	37.78	28.78
11R	6	16.03	37.41	31.41
10R	3	5.49	37.99	34.99
9R	0	0	35.75	35.75
8R	0	0	31.46	31.46
7R	0	0	27.17	27.17
6R	0	0	22.88	22.88
5R	0	0	18.59	18.59
4R	0	0	14.30	14.30
3R	0	0	10.01	10.01
2R	0	0	5.72	5.72
1R	0	0	-1.43	-1.43

= 15,032.46

$$H = \frac{\frac{My}{I}}{\frac{y^2}{I}} = \frac{15,032.46}{10,547.52}$$

$$H = 1.43$$

Load = 9

INFLUENCE LOAD AT 13L				
Point	Mom.	$\frac{My}{I}$	H_y	Total
		I		M
1L	0	0	- 1.88	-1.88
2L	0	0	7.52	7.52
3L	0	0	13.16	13.16
4L	0	0	18.80	18.80
5L	0	0	24.44	24.44
6L	0	0	30.08	30.08
7L	0	0	35.72	35.72
8L	0	0	41.36	41.36
9L	0	0	47.00	47.00
10L	23	42.09	48.64	25.64
11L	46	122.91	49.18	-3.18
12L	69	265.37	49.67	19.33
13L	92	500.39	50.10	41.90
14L	88	640.11	50.46	37.54
15L	84	793.23	50.72	33.28
16L	80	972.16	50.95	29.05
17L	76	1216.91	51.17	24.83
18L	72	1384.70	51.32	20.68
19L	68	1489.47	51.47	16.53
20L	64	1757.44	51.62	12.38
21L	60	1853.94	51.70	8.30
22L	56	1730.34	51.70	4.30
22R	52	1606.75	51.70	0.30
21R	48	1483.15	51.70	- 3.70
20R	44	1208.24	51.62	7.62
19R	40	876.16	51.47	11.47
18R	36	642.35	51.32	15.32
17R	32	512.38	51.17	19.17
16R	28	340.26	50.95	22.95
15R	24	227.21	50.72	26.72
14R	20	145.43	50.46	30.46
13R	16	87.02	50.10	34.10
12R	12	46.15	49.67	37.67
11R	8	21.38	49.18	41.18
10R	4	7.32	48.64	44.64
9R	0	0	47.00	47.00
8R	0	0	41.36	41.36
7R	0	0	35.72	35.72
6R	0	0	30.08	30.08
5R	0	0	24.44	24.44
4R	0	0	18.80	18.80
3R	0	0	13.16	13.16
2R	0	0	7.52	7.52
1R	0	0	-1.88	- 1.88

$\Sigma = 19872.91$

$$H = \frac{\sum \frac{My}{I}}{\sum \frac{y^2}{I}} = \frac{19,872.91}{10547.52} = 1.88$$

Load = 9

: Point : INFLUENCE LOAD AT 14 L :				
:	: Mom. :	: $\frac{My}{I}$:	: H_y :	: Total :
:	:	: I :	:	: M :
1L	0	0	2.33	-2.33
2L	0	0	9.32	9.32
3L	0	0	16.31	16.31
4L	0	0	23.30	23.30
5L	0	0	30.29	30.29
6L	0	0	37.28	37.28
7L	0	0	44.27	44.27
8L	0	0	51.26	51.26
9L	0	0	58.25	58.25
10L	22	40.26	60.28	38.28
11L	44	117.57	60.95	-16.95
12L	66	253.84	61.56	✓ 4.44
13L	88	478.63	62.09	25.91
14L	110	800.14	62.54	47.46
15L	105	994.04	62.86	42.14
16L	100	1215.20	63.14	36.86
17L	95	1521.14	63.42	31.58
18L	90	1605.87	63.61	26.39
19L	85	1861.92	63.80	21.20
20L	80	2196.80	63.98	16.02
21L	75	2317.43	64.08	10.92
22L	70	2162.93	64.08	5.92
22R	65	2008.44	64.08	✓ .92
21R	60	1853.94	64.08	- 4.08
20R	55	1510.30	63.98	8.98
19R	50	1095.20	63.80	13.80
18R	45	802.94	63.61	18.61
17R	40	640.48	63.42	23.42
16R	35	425.32	63.14	28.14
15R	30	284.01	62.86	32.86
14R	25	181.85	62.59	37.54
13R	20	108.78	62.09	42.09
12R	15	57.69	61.56	46.56
11R	10	26.72	60.95	50.95
10R	5	9.15	60.28	55.28
9R	0	0	58.25	58.25
8R	0	0	51.26	51.26
7R	0	0	44.27	44.27
6R	0	0	37.28	37.28
5R	0	0	30.29	30.29
4R	0	0	23.30	23.30
3R	0	0	16.31	16.31
2R	0	0	9.32	9.32
1R	0	0	2.33	2.33

$\Sigma = 24,570.59$

$$H = \frac{\sum \frac{My}{I}}{\sum \frac{y^2}{I}} = \frac{24,570.59}{10547.52} = 2.33$$

LOAD = 9

Influence Load at 15L				
Point	Mom.	$\frac{My}{I}$	H_y	Total M
1L	0	0	- 2.76	- 2.76
2L	0	0	11.04	-11.04
3L	0	0	19.32	19.32
4L	0	0	27.60	27.60
5L	0	0	35.88	35.88
6L	0	0	44.16	44.16
7L	0	0	52.44	52.44
8L	0	0	60.72	60.72
9L	0	0	69.00	69.00
10L	21	38.43	71.40	50.40
11L	42	112.22	72.20	30.20
12L	63	242.39	72.92	- 9.92
13L	84	456.88	73.55	10.45
14L	105	763.77	74.08	30.92
15L	126	1192.84	74.46	51.54
16L	180	1458.24	74.80	45.20
17L	114	1825.37	75.13	38.87
18L	108	1927.04	75.35	32.65
19L	102	2234.21	75.57	26.43
20L	96	2636.16	75.79	20.21
21L	90	2780.91	75.90	14.10
22L	84	2595.52	75.90	8.10
22R	78	2410.12	75.90	2.10
21R	72	2224.73	75.90	- 3.90
20R	66	1812.36	75.79	- 9.79
19R	60	1314.24	75.57	-15.57
18R	54	963.52	75.35	-21.35
17R	48	768.58	75.13	27.13
16R	42	510.38	74.80	32.80
15R	36	340.81	74.46	38.46
14R	30	218.22	74.08	44.08
13R	24	130.54	73.55	49.55
12R	18	69.23	72.92	54.92
11R	12	32.06	72.20	60.20
10R	6	10.98	71.40	65.40
9R	0	0	69.00	69.00
8R	0	0	60.72	60.72
7R	0	0	52.44	52.44
6R	0	0	44.16	44.16
5R	0	0	35.88	35.88
4R	0	0	27.60	27.60
3R	0	0	19.32	19.32
2R	0	0	11.04	-11.04
1R	0	0	-2.76	- 2.76

$$\Sigma = 29069.66$$

$$H = \frac{29069.66}{10,547.52} = 2.76$$

LOAD = 9

INFLUENCE LOAD AT 16L				
Point	Mom.	My	Hy	Total
		I		M
1L	0	0	-3.16	-3.16
2L	0	0	12.64	12.64
3L	0	0	22.12	22.12
4L	0	0	31.60	31.60
5L	0	0	41.08	41.08
6L	0	0	50.56	50.56
7L	0	0	60.04	60.04
8L	0	0	69.52	69.52
9L	0	0	79.00	79.00
10L	20	36.60	81.75	61.75
11L	40	106.88	82.67	42.67
12L	60	230.76	83.49	-23.49
13L	80	435.12	84.21	-4.21
14L	100	727.40	84.81	15.19
15L	120	1136.04	85.26	34.74
16L	140	1701.88	85.64	54.36
17L	133	2129.60	86.02	46.98
18L	126	2248.22	86.27	39.73
19L	119	2606.58	86.52	32.48
20L	112	3075.52	86.77	25.23
21L	105	3244.40	86.90	18.10
22L	98	3028.10	86.90	11.10
22R	91	2811.81	86.90	4.10
21R	84	2595.52	86.90	-2.90
20R	77	2114.42	86.77	-9.77
19R	70	1533.28	86.52	16.52
18R	63	1124.11	86.27	23.27
17R	56	896.67	86.02	30.02
16R	49	595.45	85.64	36.64
15R	42	397.61	85.26	43.26
14R	35	254.58	84.81	49.81
13R	28	152.29	84.21	56.21
12R	21	80.77	83.49	62.49
11R	14	37.41	82.67	68.67
10R	7	12.81	81.75	74.75
9R	0	0	79.00	79.00
8R	0	0	69.52	69.52
7R	0	0	60.04	60.04
6R	0	0	50.56	50.56
5R	0	0	41.08	41.08
4R	0	0	31.60	31.60
3R	0	0	22.12	22.12
2R	0	0	12.64	12.64
1R	0	0	-3.16	-3.16

$\Sigma = 33,313.24$

$$H = \frac{33,313.24}{10,547.52} = 3.16$$

Load = 9

Pt.: INFLUENCE LOAD AT 17L				
	Mom.	My	Hy	Total
	I	I		M
1L	0	0	- 3.53	- 3.53
2L	0	0	14.12	14.12
3L	0	0	24.71	24.71
4L	0	0	35.30	35.30
5L	0	0	45.89	45.89
6L	0	0	56.48	56.48
7L	0	0	67.07	67.07
8L	0	0	77.66	77.66
9L	0	0	88.25	88.25
10L	19	34.77	91.32	72.32
11L	38	101.54	92.34	54.34
12L	57	219.22	93.26	36.26
13L	76	413.36	94.07	-18.07
14L	95	691.03	94.75	4 .25
15L	114	1079.24	95.24	13 76
16L	133	1616.22	95.66	37 34
17L	152	2433.82	96.09	55.91
18L	144	2569.39	96.37	47.63
19L	136	2678.94	96.65	39.35
20L	128	3514.88	96.93	31.07
21L	120	3707.88	97.08	22.92
22L	112	3460.69	97.08	14.92
22R	104	3213.50	97.08	6 92
21R	96	2966.30	97.08	-1.08
20R	88	2416.48	96.93	-8.93
19R	80	1752.32	96.65	16.65
18R	72	1284.70	96.37	24.36
17R	64	1024.77	96.09	32.09
16R	56	680.51	95.66	39.66
15R	48	454.48	95.24	47.24
14R	40	290.96	94.75	54.75
13R	32	174.05	94.07	62.07
12R	24	92.30	93.26	69.26
11R	16	42.74	92.34	76.34
10R	8	14.64	91.32	83.32
9R	0	0	88.25	88.25
8R	0	0	77.66	77.66
7R	0	0	67.07	67.07
6R	0	0	56.48	56.48
5R	0	0	45.89	45.89
4R	0	0	35.30	35.30
3R	0	0	24.71	24.71
2R	0	0	14.12	14.12
1R	0	0	-3.53	-3.53

$$\Sigma = 37,228.67$$

$$H = \frac{37,228.67}{10,547.52} = 3.53$$

Load = 9

Point:	INFLUENCE LOAD AT 18 L			
: Mom.	: My	: Hy	: Total	:
:	: I	:	: M	:
1L	0	0	- 3.86	- 3.86
2L	0	0	-15.44	-15.44
3L	0	0	27.02	-27.02
4L	0	0	38.60	-38.60
5L	0	0	50.18	-50.18
6L	0	0	61.76	-61.76
7L	0	0	73.34	-73.34
8L	0	0	84.92	-84.92
9L	0	0	96.50	-96.50
10L	18	32.94	99.86	81.86
11L	36	96.19	100.98	64.98
12L	54	207.68	101.98	47.98
13L	72	391.61	102.87	30.87
14L	90	654.66	103.60	-13.60
15L	108	1022.44	104.14	- 3.86
16L	126	1531.15	104.61	-21.39
17L	144	2306.73	105.07	38.93
18L	162	2890.57	105.38	56.62
19L	153	3351.31	105.69	47.31
20L	144	3954.24	106.00	38.00
21L	135	4171.37	106.15	28.85
22L	126	3893.27	106.15	19.85
22R	117	3615.18	106.15	10.85
21R	108	3337.09	106.15	- 1.85
20R	99	2718.54	106.00	- 7.00
19R	90	1971.36	105.69	15.69
18R	81	1445.28	105.38	24.38
17R	72	1152.86	105.07	33.07
16R	63	765.58	104.61	41.61
15R	54	511.22	104.14	50.14
14R	45	327.33	103.60	58.60
13R	36	195.80	102.87	66.87
12R	27	103.84	101.98	74.98
11R	18	48.10	100.98	82.98
10R	9	16.47	99.86	90.86
9R	0	0	96.50	96.50
8R	0	0	84.92	84.92
7R	0	0	73.34	73.34
6R	0	0	61.76	61.76
5R	0	0	50.18	50.18
4R	0	0	38.60	38.60
3R	0	0	27.02	27.02
2R	0	0	-15.44	15.44
1R	0	0	- 3.86	-3.86

$$\Sigma = 40,711.81$$

$$H = \frac{40,711.81}{10,547.52} = 3.86$$

Load = 9

Influence Load at 19L					
Point :	Mom.	My	Hy	Total	
:	:	I	:	Mom.	:
1L	0	0	-4.14	-4.14	:
2L	0	0	16.56	16.56	:
3L	0	0	28.98	28.98	:
4L	0	0	41.40	41.40	:
5L	0	0	53.82	53.82	:
6L	0	0	66.24	66.24	:
7L	0	0	78.66	78.66	:
8L	0	0	91.08	91.08	:
9L	0	0	103.50	103.50	:
10L	17	51.11	107.10	90.10	:
11L	34	90.85	108.30	74.30	:
12L	51	196.15	109.38	58.38	:
13L	68	369.85	110.33	42.33	:
14L	85	618.29	111.12	26.12	:
15L	102	965.63	111.70	-9.70	:
16L	119	1446.09	112.19	-6.81	:
17L	136	2177.63	112.69	23.31	:
18L	153	2729.98	113.02	39.98	:
19L	170	3723.68	113.35	56.65	:
20L	180	4393.60	113.68	46.32	:
21L	150	4634.85	113.85	36.15	:
22L	140	4325.86	113.85	26.13	:
22R	130	4016.87	113.85	16.15	:
21R	120	3707.88	113.85	-6.15	:
20R	110	3020.60	113.68	-3.68	:
19R	100	2190.40	113.35	13.35	:
18R	90	1605.87	113.02	23.02	:
17R	80	1280.96	112.69	32.69	:
16R	70	850.64	112.19	42.19	:
15R	60	568.02	111.70	51.70	:
14R	50	363.70	111.12	61.12	:
13R	40	217.56	110.33	70.33	:
12R	30	115.38	109.38	79.38	:
11R	20	53.44	108.30	88.30	:
10R	10	18.30	107.10	97.10	:
9R	0	0	103.50	103.50	:
8R	0	0	91.08	91.08	:
7R	0	0	78.66	78.66	:
6R	0	0	66.24	66.24	:
5R	0	0	53.82	53.82	:
4R	0	0	41.40	41.40	:
3R	0	0	28.98	28.98	:
2R	0	0	16.56	16.56	:
1R	0	0	-4.14	-4.14	:

= 43,713.19

$$H = \frac{43,713.19}{10,547.52} = 4.14$$

Load = 9

Influence Load at 20L				
Point	Mom.	My	Hy	Total
		I		Mom.
1L	0	0	-4.37	-4.37
2L	0	0	17.48	17.48
3L	0	0	30.59	30.59
4L	0	0	43.70	43.70
5L	0	0	56.81	56.81
6L	0	0	69.92	69.92
7L	0	0	83.03	83.03
8L	0	0	96.14	96.14
9L	0	0	109.25	109.25
10L	16	29.28	113.05	97.05
11L	32	85.50	114.32	82.32
12L	48	184.61	115.46	67.46
13L	64	348.10	116.46	52.46
14L	80	581.92	117.29	37.29
15L	96	908.83	117.90	21.90
16L	112	1361.02	118.43	- 6.43
17L	128	2049.54	118.95	✓ 9.05
18L	144	2569.39	119.30	24.70
19L	160	3504.64	119.65	40.15
20L	176	4832.96	120.00	56.00
21L	165	5098.34	120.18	44.82
22L	154	4758.45	120.18	33.82
22R	143	4418.56	120.18	22.82
21R	132	4078.67	120.18	11.82
20R	121	3322.66	120.00	✓ 1.00
19R	110	2409.44	119.65	-9.65
18R	99	1766.46	119.30	20.30
17R	88	1409.06	118.95	30.95
16R	77	935.70	118.43	41.43
15R	66	624.82	117.90	51.90
14R	55	400.07	117.29	52.29
13R	44	239.32	116.46	72.46
12R	33	126.92	115.46	82.46
11R	22	58.78	114.32	92.32
10R	11	20.13	113.05	102.05
9R	0	0	109.25	109.25
8R	0	0	96.14	96.14
7R	0	0	83.03	83.03
6R	0	0	69.92	69.92
5R	0	0	56.81	56.81
4R	0	0	43.70	43.70
3R	0	0	30.59	30.59
2R	0	0	17.48	17.48
1R	0	0	-4.37	4.37

= 46,123.17

$$H = \frac{46,123.17}{10,547.52} = 4.37$$

Load = 9

Influence Load at 21L				
: Point :	Mom.	: My	: Hy	: Total
:	:	: I	:	: Mom.
1L	0	0	-4.53	-4.53
2L	0	0	18.12	18.12
3L	0	0	31.71	31.71
4L	0	0	45.30	45.30
5L	0	0	58.89	58.89
6L	0	0	72.48	72.48
7L	0	0	86.07	86.07
8L	0	0	99.66	99.66
9L	0	0	113.25	113.25
10L	15	27.45	117.19	102.19
11L	30	80.16	118.50	88.50
12L	45	173.07	119.68	74.68
13L	60	326.34	120.72	60.72
14L	75	545.55	121.59	46.59
15L	90	852.03	122.22	32.22
16L	105	1275.96	122.76	17.76
17L	120	1921.44	123.31	-3.31
18L	135	2408.81	123.67	-11.33
19L	150	3285.60	124.03	25.97
20L	165	4530.90	124.39	40.61
21L	180	5561.82	124.58	55.42
22L	168	5191.03	124.58	43.42
22R	156	4820.24	124.58	31.42
21R	144	4449.46	124.58	19.42
20R	132	3624.72	124.39	7.61
19R	120	2628.48	124.03	-4.03
18R	108	1927.04	123.67	15.67
17R	96	1537.15	123.31	27.31
16R	84	1020.77	122.76	38.76
15R	72	681.62	122.22	50.22
14R	60	436.44	121.59	61.59
13R	48	261.07	120.72	72.72
12R	36	138.46	119.68	83.68
11R	24	64.13	118.50	94.50
10R	12	21.96	117.19	105.19
9R	0	0	113.25	113.25
8R	0	0	99.66	99.66
7R	0	0	86.07	86.07
6R	0	0	72.48	72.48
5R	0	0	58.89	58.89
4R	0	0	45.30	45.30
3R	0	0	31.71	31.71
2R	0	0	18.12	18.12
1R	0	0	- 4.53	-4.53

= 47,791.70


$$H = \frac{47,791.70}{10,547.52} = 4.53$$


Load = 9

Influence Load at 22L				
Point	Mom.	My	Hy	Total
		I		Mom.
1L	0	0	-4.61	-4.61
2L	0	0	18.44	18.44
3L	0	0	32.27	32.27
4L	0	0	46.10	46.10
5L	0	0	59.93	59.93
6L	0	0	73.76	73.76
7L	0	0	87.59	87.59
8L	0	0	101.42	101.42
9L	0	0	115.25	115.25
10L	14	25.62	119.26	105.26
11L	28	74.62	120.60	92.60
12L	42	161.53	121.80	79.80
13L	56	304.58	122.86	66.86
14L	70	509.18	123.73	53.73
15L	84	795.23	124.38	40.38
16L	98	1190.90	124.95	26.93
17L	112	1793.34	125.48	-13.48
18L	126	2248.22	125.85	1.15
19L	140	3066.56	126.22	13.78
20L	154	4228.84	126.59	27.41
21L	168	5191.03	126.78	41.22
22L	182	5623.62	126.78	55.22
22R	169	5221.93	126.78	42.22
21R	156	4820.24	126.78	29.22
20R	143	3926.78	126.59	16.41
19R	130	2847.52	126.22	3.78
18R	117	2087.63	125.85	-8.85
17R	104	1665.25	125.48	21.48
16R	91	1105.83	124.93	33.93
15R	78	738.43	124.38	46.38
14R	65	472.81	123.73	58.73
13R	52	282.83	122.86	70.86
12R	39	149.99	121.80	82.80
11R	26	69.47	120.60	94.60
10R	13	23.79	119.26	106.26
9R	0	0	115.25	115.25
8R	0	0	101.42	101.42
7R	0	0	87.59	87.59
6R	0	0	73.76	73.76
5R	0	0	59.93	59.93
4R	0	0	46.10	46.10
3R	0	0	32.27	32.27
2R	0	0	18.44	18.44
1R	0	0	-4.61	-4.61


= 48,625.97

$$H = \frac{48,625.97}{10,547.58} = 4.61$$





INFLUENCE LINES FOR MOMENT



Point at which Load Acts

INFLUENCE LINES FOR REACTIONS

CALCULATION OF DEAD LOAD AT VARIOUS POINTS.

Concrete is assumed to weigh 150 lbs. per cu. ft.

4" concrete paving is assumed, weighing 50 lbs. per sq. ft.

Pt. 22

$$\begin{array}{rcl} \text{Rib} - (2.0 \times 1.0 \times 3.0) \times 150 & = & 900\# \\ \text{Paving} - 3.0 \times 50 & = & 150\# \\ & & \hline & & 1050\# \end{array}$$

Pt. 21

$$\text{Same as Pt. 22} = 1050\#$$

Pt. 20

$$\begin{array}{rcl} \text{Rib} - (2.08 \times 1.0 \times 3.0) \times 150 & = & 936\# \\ \text{Paving} - & & 150\# \\ & & \hline & & 1086\# \end{array}$$

Pt. 19

$$\begin{array}{rcl} \text{Rib} (2.25 \times 1.0 \times 3.0) \times 150 & = & 1017\# \\ \text{Paving} & & 150 \\ & & \hline & & 1167\# \end{array}$$

Pt. 18

$$\begin{array}{rcl} \text{Rib} (2.42 \times 1.0 \times 3.0) \times 150 & = & 1090\# \\ \text{Paving} - & & 150 \\ & & \hline & & 1240\# \end{array}$$

Pt. 17

$$\begin{array}{rcl} \text{Rib} (2.58 \times 1.0 \times 3.0) \times 150 & = & 1161\# \\ \text{Paving} - & & 150\# \\ & & \hline & & 1311\# \end{array}$$

Pt. 16

$$\begin{array}{rcl} \text{Rib} (2.83 \times 1.0 \times 3.0) \times 150 & = & 1273\# \\ \text{Paving} - & & 150 \\ & & \hline & & 1423\# \end{array}$$

Pt. 15

$$\begin{array}{rcl} \text{Rib} (3.08 \times 1.0 \times 3.0) \times 150 & = & 1387\# \\ \text{Paving} - & & 150\# \\ & & \hline & & 1537\# \end{array}$$

Pt. 14

$$\begin{array}{rcl} \text{Rib} (3.37 \times 1.0 \times 3.0) \times 150 & = & 1518\# \\ \text{Paving} - & & 150\# \\ & & \hline & & 1668\# \end{array}$$

Pt. 13

$$\begin{array}{rcl} \text{Rib} (3.75 \times 1.0 \times 3.0) \times 150 & = & 1688\# \\ \text{Paving} - & & 150\# \\ & & \hline & & 1838\# \end{array}$$

Pt. 12

$$\begin{array}{rcl} \text{Rib} (4.21 \times 1.0 \times 3.0) \times 150 & = & 1892\# \\ \text{Paving} & & 150\# \\ & & \hline & & 2042\# \end{array}$$

Pt. 11

$$\begin{array}{rcl} \text{Rib} (4.75 \times 1.0 \times 3.0) \times 150 & = & 2138\# \\ \text{Paving} - & & 150\# \\ & & \hline & & 2288\# \end{array}$$

Calculation of Dead Loads - Cont'd.

Pt. 10
 Rib $(5.33 \times 1.0 \times 3.0) 150 = 2400\#$
 Paving $\frac{150\#}{2550\#}$

Pt. 9
 Knee $(5.0 \times 5.0 \times 1.0) 150 = 3750\#$
 Paving $2.25 \times 50 \frac{115}{3865}$

Pt. 8
 Leg. $(5.69 \times 1.0 \times 3.0) 150 = 2560\#$

Pt. 7
 $(5.35 \times 1.0 \times 3.0) 150 = 2405\#$

Pt. 6
 $(5.02 \times 1.0 \times 3.0) 150 = 2260\#$

Pt. 5
 $(4.69 \times 1.0 \times 3.0) 150 = 2110\#$

Pt. 4
 $(4.33 \times 1.0 \times 3.0) 150 = 1950\#$

Pt. 3
 $(4.00 \times 1.0 \times 3.0) 150 = 1800\#$

Pt. 2
 $(3.67 \times 1.0 \times 3.0) 150 = 1650\#$

Pt. 1
 $(2.0 \times 2.0 \times 1.0) / (2.0 \times 9.0 \times 1.0)$
 $/ (2.5 \times 1.0 \times 3.67) 150 = 4680\#$

DEAD LOAD MOMENT FACTORS AND MOMENTS

:Ld.:	Ld.:	: Point 2		: Point 3		: Point 4		: Point 5		: Point 6		: Load	:
:at :	:	MF	M	MF	M	MF	M	MF	M	MF	M	: at	:
:Pt.:	:	:	:	:	:	:	:	:	:	:	:	: Point	:
10L	2550	.21	-536	.38	-970	.53	-1352	.70	-1785	.83	-2115	10L	:
11L	2288	.42	962	.75	1717	1.04	2381	1.38	3160	1.65	3780	11L	:
12L	2042	.62	1267	1.12	2286	1.59	3245	2.07	4225	2.52	5140	12L	:
13L	1838	.82	1508	1.47	2720	2.12	3900	2.71	4980	3.33	6120	13L	:
14L	1668	1.01	1685	1.82	3038	2.60	4340	3.37	5625	4.15	6920	14L	:
15L	1537	1.21	1860	2.15	3304	3.05	4690	4.00	6150	4.92	7565	15L	:
16L	1423	1.41	2008	2.47	3520	3.52	5010	4.56	6490	5.61	7990	16L	:
17L	1311	1.57	2059	2.72	3566	3.89	5100	5.10	6685	6.28	8230	17L	:
18L	1240	1.65	2045	3.00	3720	4.30	5333	5.56	6890	6.87	8520	18L	:
19L	1167	1.80	2100	3.25	3790	4.61	5375	6.00	7000	7.37	8600	19L	:
20L	1086	1.93	2095	3.40	3690	4.82	5235	6.32	6860	7.75	8410	20L	:
21L	1050	2.02	2121	3.50	3675	5.03	5280	6.54	6870	8.07	8480	21L	:
22L	1050	2.04	2142	3.58	3760	5.14	5400	6.66	6990	8.20	8610	22L	:
22R	1050	2.04	2142	3.58	3760	5.14	5400	6.66	6990	8.20	8610	22R	:
21R	1050	2.02	2121	3.50	3675	5.03	5280	6.54	6870	8.07	8480	21R	:
20R	1086	1.93	2095	3.40	3690	4.82	5235	6.32	6860	7.75	8410	20R	:
19R	1167	1.80	2100	3.25	3790	4.61	5375	6.00	7000	7.37	8600	19R	:
18R	1240	1.65	2045	3.00	3720	4.30	5333	5.56	6890	6.87	8520	18R	:
17R	1311	1.57	2059	2.72	3566	3.89	5100	5.10	6685	6.28	8230	17R	:
16R	1423	1.41	2008	2.47	3520	3.52	5010	4.56	6490	5.61	7990	16R	:
15R	1537	1.21	1860	2.15	3304	3.05	4690	4.00	6150	4.92	7565	15R	:
14R	1668	1.01	1685	1.82	3038	2.60	4340	3.37	5625	4.15	6920	14R	:
13R	1838	.82	1508	1.47	2720	2.12	3900	2.71	4980	3.33	6120	13R	:
12R	2042	.62	1267	1.12	2286	1.59	3245	2.07	4225	2.52	5140	12R	:
11R	2288	.42	962	.75	1717	1.04	2381	1.38	3160	1.65	3780	11R	:
10R	2550	.21	-536	.38	-970	.53	-1352	.70	-1785	.83	-2115	10R	:
Totals		-43,776		-79,512		-113,282		-147,420		-180,960			

:Load:	: Point 7	: Point 8	: Point 9	: Point 10	: Point 11	:Load :
: at :Load: MF : M :MF :	M : MF :	M : MF :	M : MF :	M : MF :	M : MF :	: at :
:Pt. :	:	:	:	:	:	:Pt. :
10L 2550 -1.02 -2600 -1.19 -3035 -1.35 - 3440 1.50 3821 1.38 3519 10L						
11L 2288 2.03 4650 2.36 5410 2.66 6090 .00 2.65 6020 11L						
12L 2042 3.02 6165 3.50 7150 4.00 8170 -1.55 -3163 1.15 2350 12L						
13L 1838 4.00 7355 4.62 8490 5.24 9645 -2.85 5240 - .35 - 644 13L						
14L 1668 4.92 8210 5.70 9520 6.50 10840 4.27 7130 -1.88 3135 14L						
15L 1537 5.80 8920 6.73 10330 7.65 11750 5.60 8605 3.37 5180 15L						
16L 1423 6.67 9500 7.70 10970 8.75 12450 6.86 9770 4.75 6760 16L						
17L 1311 7.45 9760 8.63 11400 9.82 12970 8.07 10580 6.08 7965 17L						
18L 1240 8.18 10150 9.45 11720 10.73 13320 9.15 11350 7.25 8990 18L						
19L 1167 8.73 10180 10.12 11800 11.50 13420 10.10 11780 8.25 9625 19L						
20L 1086 9.23 10020 10.70 11620 12.12 13150 10.81 11730 9.15 9935 20L						
21L 1050 9.56 10030 11.08 11620 12.55 13180 11.37 11930 9.85 10235 21L						
22L 1050 9.75 10230 11.30 11870 12.80 13430 11.70 12280 10.30 10820 22L						
22R 1050 9.75 10230 11.30 11870 12.80 13430 11.80 12380 10.50 11020 22R						
21R 1050 9.56 10030 11.08 11620 12.55 13180 11.70 12280 10.50 11020 21R						
20R 1086 9.23 10020 10.70 11620 12.12 13150 11.38 12360 10.27 11130 20R						
19R 1167 8.73 10180 10.12 11800 11.50 13420 10.80 12590 9.81 11425 19R						
18R 1240 8.18 10150 9.45 11720 10.73 13320 10.13 12580 9.23 11430 18R						
17R 1311 7.45 9760 8.63 11400 9.82 12970 9.30 12190 8.50 11130 17R						
16R 1423 6.67 9500 7.70 10970 8.75 12450 8.30 11820 7.63 10870 16R						
15R 1537 5.80 8920 6.73 10330 7.65 11750 7.28 11180 6.72 10320 15R						
14R 1668 4.92 8210 5.70 9520 6.50 10840 6.15 10270 5.68 9460 14R						
13R 1838 4.00 7355 4.62 8490 5.24 9645 4.99 9190 4.58 8420 13R						
12R 2042 3.02 6165 3.50 7150 4.00 8170 3.90 7965 3.52 7190 12R						
11R 2288 2.03 4650 2.36 5410 2.66 6090 2.70 4450 2.40 5490 11R						
10R 2550 -1.02 -2600 -1.19 -3035 -1.35 -3440 1.35 -2600 1.20 -3061 10R						

Totals-	-215,540	-249,870	-283,710	-231,592	- 183,316
---------	----------	----------	----------	----------	-----------

: Load	: Point 12	: Point 13	: Point 14	: Point 15	: Point 16	: Load	:
: at :	: MF	: M	: MF	: M	: MF	: M	:
: Pt.:Load:	:	:	:	:	:	:	: at :
:	:	:	:	:	:	:	:Point :
10L 2550	/1.25	/3188	/1.12	/2857	/1.98	/2498	/1.88
11L 2288	2.50	5725	2.25	5150	2.02	4625	1.77
12L 2042	3.92	8010	3.43	6805	3.05	6230	2.70
13L 1838	2.18	4010	4.65	8550	4.15	7635	3.68
14L 1668	/1.50	/834	2.87	4790	5.27	8800	4.65
15L 1537	-1.10	-1690	/1.15	/1768	3.42	5260	5.70
16L 1423	2.64	3760	-0.50	- 711	/1.70	/2420	3.66
17L 1311	4.08	5340	2.00	2622	.00	-	2.08
18L 1240	5.32	6600	3.43	4255	-1.50	-1860	/1.44
19L 1167	6.50	7580	4.70	5485	2.90	3381	-1.12
20L 1086	7.48	8115	5.82	6320	4.18	4540	2.45
21L 1050	8.32	8735	6.75	7090	5.20	5460	3.58
22L 1050	8.85	9290	7.40	7765	6.00	6300	4.50
22R 1050	9.20	9660	7.82	8210	6.54	6870	5.18
21R 1050	9.30	9765	8.07	8470	6.85	7190	5.59
20R 1086	9.17	9960	8.05	8740	6.90	7495	5.78
19R 1167	8.82	10280	7.80	9100	6.80	7935	5.75
18R 1240	8.33	10325	7.42	9200	6.50	8060	5.58
17R 1311	7.70	10090	6.93	9085	6.12	8025	5.25
16R 1423	6.95	9900	6.25	8900	5.50	7835	4.82
15R 1537	6.08	9350	5.50	8455	4.93	7575	4.27
14R 1668	5.18	8650	4.70	7840	4.18	6970	3.66
13R 1838	4.20	7720	3.78	6950	3.42	6290	2.98
12R 2042	3.22	6580	2.92	5965	2.62	5360	2.33
11R 2288	2.18	4980	2.00	4576	1.75	4005	1.55
10R 2550	-1.08	-2755	-1.00	-2550	-0.88	- 2242	-0.79
Totals -	-139,358	-102,369	-69,925	-42,034	-19,770		

Load	Point 17	Point 18	Point 19	Point 20	Point 21	Load
at	MF	M	MF	M	MF	at
Pt.:Load:	:	:	:	:	:	Point:
10L 2550	/.63	/1607	/.51	/1301	/.41	/1047
11L 2288	1.27	2907	1.05	2405	.83	1900
12L 2042	2.00	4084	1.65	3370	1.27	2595
13L 1838	2.70	4965	2.28	4190	1.78	3275
14L 1668	3.50	5840	2.85	4760	2.33	3890
15L 1537	4.28	6580	3.64	5600	2.90	4460
16L 1423	5.20	7400	4.42	6290	3.60	5125
17L 1311	6.19	8115	5.27	6910	4.35	5700
18L 1240	4.25	5270	6.28	7790	5.22	6490
19L 1167	2.57	2995	4.45	5190	6.27	7310
20L 1086	/.98	/1063	2.78	3017	4.48	4870
21L 1050	-.38	- 399	/1.25	/1312	2.90	3043
22L 1050	1.50	1575	.00	-	1.50	1575
22R 1050	2.40	2520	-1.00	-1050	/.41	/431
21R 1050	3.04	3193	1.75	1838	-.48	-504
20R 1086	3.47	3765	2.28	2475	1.08	1172
19R 1167	3.65	4255	2.58	3010	1.53	1784
18R 1240	3.70	4590	2.70	3350	1.78	2207
17R 1311	3.55	4650	2.70	3540	1.90	2490
16R 1423	3.35	4765	2.60	3700	1.90	2705
15R 1537	3.06	4710	2.38	3660	1.77	2720
14R 1668	2.62	4370	2.07	3455	1.54	2570
13R 1838	2.15	2955	1.72	3162	1.32	2425
12R 2042	1.68	3430	1.33	2717	1.06	2165
11R 2288	1.16	2658	.92	2106	.75	1718
10R 2550	-.58	-1480	.46	- 1173	.38	-970

Totals /1511 /16,899 /28,271 /36,038 /44,077

: Load :		Point 22	
: At :	Load :	MF :	M :
:Point :	:	:	:
: 10L :	2550	: .09	: 230
: 11L :	2288	: .19	: 435
: 12L :	2042	: .32	: 654
: 13L :	1838	: .50	: 919
: 14L :	1668	: .67	: 1117
: 15L :	1537	: .86	: 1322
: 16L :	1423	: 1.23	: 1750
: 17L :	1311	: 1.66	: 2175
: 18L :	1240	: 2.20	: 2730
: 19L :	1167	: 2.90	: 3380
: 20L :	1086	: 3.72	: 4040
: 21L :	1050	: 4.60	: 5040
: 22L :	1050	: 6.13	: 6435
: 22R :	1050	: 4.70	: 4935
: 21R :	1050	: 3.48	: 3655
: 20R :	1086	: 2.52	: 2717
: 19R :	1167	: 1.78	: 2075
: 18R :	1240	: 1.20	: 1488
: 17R :	1311	: .78	: 1022
: 16R :	1423	: .46	: 655
: 15R :	1537	: .25	: 385
: 14R :	1668	: .10	: 167
: 13R :	1838	: 0	: -
: 12R :	2042	: .07	: - 143
: 11R :	2288	: .10	: 229
: 10R :	2550	: .05	: - 128

46,826

Components of Reactions Due to Dead Load.

$$V_1 = V_r = 43,528\#$$

: Load :	D.L. :	HF :	H :	:
: at :	:	:	:	:
: Point :	:	:	:	:
: 10 :	2550 :	.053 :	133 :	:
: 11 :	2288 :	.106 :	243 :	:
: 12 :	2042 :	.158 :	323 :	:
: 13 :	1838 :	.209 :	384 :	:
: 14 :	1668 :	.258 :	431 :	:
: 15 :	1537 :	.307 :	472 :	:
: 16 :	1423 :	.351 :	500 :	:
: 17 :	1311 :	.391 :	512 :	:
: 18 :	1240 :	.430 :	534 :	:
: 19 :	1167 :	.460 :	536 :	:
: 20 :	1088 :	.485 :	528 :	:
: 21 :	1050 :	.505 :	530 :	:
: 22 :	1050 :	.511 :	538 :	:

$$5662 \times 2 = 11,334\#$$

NORMAL THRUSTS DUE TO DEAD LOAD

Point 1

$$N = V = 43,528 \#$$

Point 2

$$N = 43,528 - 4680 = 38,848\#$$

Point 3

$$N = 38,848 - 1650 = 37,198\#$$

Point 4

$$N = 37,198 - 1800 = 35,398\#$$

Point 5

$$N = 35,398 - 1950 = 33,448\#$$

Point 6

$$N = 33,448 - 2110 = 31,338\#$$

Point 7

$$N = 31,338 - 2260 = 29,078\#$$

Point 8

$$N = 29,078 - 2405 = 27,673\#$$

Point 9

$$N = (27,673 - 2560) \cdot .71 / (11,334 \times .71) = 25,850\#$$

(Since components of H and V at 45° make up N)

Points 10-22

$$N = H = 11,334\#$$

TEMPERATURE STRESSES

$$C = .0000065$$

$$t = /50 \text{ or } -30$$

$$l = 81$$

$$E = \text{Modulus of elasticity of concrete} = 144 \times 10^6 = 288,000,000 \text{ lbs./sq.in.}$$

$$S = 3 \text{ ft.}$$

$$H = \frac{E \epsilon l}{3 \sum \frac{y^3}{I}}$$

$$H = / \frac{288,000,000 \times .0000065 \times 50 \times 81}{3 \times 10,547.52} = / 238$$

$$H = - \frac{288,000,000 \times .0000065 \times 30 \times 81}{3 \times 10,547.52} = - 144$$

Point :	Y :	-Hy :	/ Hy :
2 :	4.0 :	-953 :	/ 576 :
3 :	7.0 :	-1665 :	/ 1008 :
4 :	10.0 :	-2380 :	/ 1440 :
5 :	13.0 :	-3095 :	/ 1873 :
6 :	16.0 :	-3810 :	/ 2305 :
7 :	19.0 :	-4525 :	/ 2735 :
8 :	22.0 :	-5240 :	/ 3170 :
9 :	25.0 :	-5960 :	/ 3600 :
10 :	25.87 :	-6160 :	/ 3730 :
11 :	26.16 :	-6230 :	/ 3762 :
12 :	26.42 :	-6290 :	/ 3810 :
13 :	26.65 :	-6350 :	/ 3840 :
14 :	26.84 :	-6400 :	/ 3867 :
15 :	26.98 :	-6425 :	/ 3885 :
16 :	27.10 :	-6450 :	/ 3905 :
17 :	27.22 :	-6490 :	/ 3920 :
18 :	27.30 :	-6510 :	/ 3935 :
19 :	27.38 :	-6520 :	/ 3942 :
20 :	27.46 :	-6540 :	/ 3958 :
21 :	27.50 :	-6550 :	/ 3962 :
22 :	27.50 :	-6550 :	/ 3962 :

Points 2 to 8 N = 0

Points 10 to 22

$$-N = /H = 238$$

$$/N = -H = 144$$


$$\text{Point 9: } /N = 144 \times .71 = -102, -N = /238 \times .71 = /169$$

EARTH PRESSURE RT.

Point	Vertical Distance from 0	Vertical Distance Between	Earth Pressure Right Horizontal Loads	Sum of Loads	Inc. of Mom.	Partial From 0 = X	Nor. Dist.	Mom B = Vx	Sub-Total M _a /M _b
H1	0	0.5	18,184	18,184	6,092	/6092			
E1	.5	.5	2,044	10,140	5,070	/11162			
1R	1.0	1.5		10,140	15,210	/26372			/26372
E2	2.5	1.5	2,205	7,935	11,890	/38262			
2R	4.0	1.5		7,935	11,890	/50152			/50152
E3	5.5	1.5	1,935	6,000	9,000	/59152			
3R	7.0	1.5		6,000	9,000	/68152			/68152
E4	8.5	1.5	1,665	4,335	6,525	/74,677			
4R	10.0	1.5		4,335	6,525	/81202			/81202
E5	11.5	1.5	1,395	2,940	4,410	/85612			
5R	13.0	1.5		2,940	4,410	/90022			/90022
E6	14.5	1.5	1,125	1,815	2,720	/92742			
6R	16.0	1.5		1,815	2,720	/95462			/95462
E7	17.5	1.5	855	960	1,440	/96902			
7R	19.0	1.5		960	1,440	/98342			/98342
E8	20.5	1.5	585	375	563	/98905			
8R	22.0	1.5		375	563	/99468			/99468
39	23.5	1.5	315	60	90	/99558			
9R	25.0	.87		60	52	/99610			/99610
10R	25.87	.15		60	9	/99619	3	-3690	/99619
E10	26.02	.14	60	0	0	/99619			
11R	26.16	.26				/99619	6	-7380	/99619
12R	26.42	.23				/99619	9	-11070	/99619
13R	26.65	.19				/99619	12	-14760	/99619
14R	26.84	.14				/99619	15	-18450	/99619
15R	26.98	.12				/99619	18	-22140	/99619
16R	27.10	.12				/99619	21	-25830	/99619
17R	27.22	.08				/99619	24	-29520	/99619
18R	27.30	.08				/99619	27	-33210	/99619
19R	27.38	.08				/99619	30	-36900	/99619
20R	27.46	.04				/99619	33	-40590	/99619
21R	27.50	.0				/99619	36	-44280	/99619
22R	27.50					/99619	39	-27970	/99619
22L	27.50					/99619	42	-51660	/99619
21L	27.50					/99619	45	-55350	/99619
20L	27.46					/99619	48	-59040	/99619
19L	27.38					/99619	51	-62730	/99619
18L	27.30					/99619	54	-66420	/99619
17L	27.22					/99619	57	-70110	/99619
16L	27.10					/99619	60	-73800	/99619
15L	26.98					/99619	63	-77490	/99619
14L	26.84					/99619	66	-81180	/99619
13L	26.65					/99619	69	-84870	/99619
12L	26.42					/99619	72	-88560	/99619

EARTH PRESSURE RIGHT (Cont'd.)

: 11L	: 26.16	:	:	:	:	:	: /99,619: 75:-92,250	: /7,369 :
: 10L	: 25.87	:	:	:	:	:	: /99,619: 78:-95,940	: /8,679 :
: 9L	: 25.0	:	:	:	:	:	: /99,619: 81:-99,619	:
: 8L	: 22.0	:	:	:	:	:	: /99,619: 81:-99,619	:
: 7L	: 19.0	:	:	:	:	:	: /99,619: 81:-99,619	:
: 6L	: 16.0	:	:	:	:	:	: /99,619: 81:-99,619	:
: 5L	: 13.0	:	:	:	:	:	: /99,619: 81:-99,619	:
: 4L	: 10.0	:	:	:	:	:	: /99,619: 81:-99,619	:
: 3L	: 7.0	:	:	:	:	:	: /99,619: 81:-99,619	:
: 2L	: 4.0	:	:	:	:	:	: /99,619: 81:-99,619	:
: 1L	: 1.0	:	:	:	:	:	: /99,619: 81:-99,619	:



Points 2 to 8

$$N = V = 1429$$

Points 10 to 22

$$N = H = 1352$$

Point 9L

$$N = (.71 \times 1352) / (.71 \times 1429) = /2330$$

Point 9R

$$N = (.71 \times 1352) - (.71 \times 1429) = /300$$

EARTH PRESSURE RIGHT - Cont'd.

Point	Y	I	$\frac{My}{I}$	H_y	Total Mom.
1R	1	62.06		- 1,852	-
2R	4	4.51	43,500	- 7,408	442,744
3R	7	5.80	82,300	-12,964	455,188
4R	10	7.32	111,000	-18,520	462,682
5R	13	9.76	120,000	-24,076	465,946
6R	16	11.86	128,800	-29,632	465,830
7R	19	14.29	130,700	-35,188	463,154
8R	22	17.10	128,000	-40,744	458,724
9R	25	19.96	124,800	-46,300	453,310
10R	25.87	14.14	175,300	-48,000	447,929
11R	26.16	9.79	246,200	-48,400	443,839
12R	26.42	6.87	340,500	-49,000	439,549
13R	26.65	4.90	461,500	-49,400	435,449
14R	26.84	3.69	591,000	-49,700	431,469
15R	26.98	2.85	733,000	-50,000	427,479
16R	27.10	2.23	897,000	-50,200	423,589
17R	27.22	1.70	1,122,000	-50,500	419,599
18R	27.30	1.53	1,183,000	-50,600	415,809
19R	27.38	1.25	1,373,000	-50,700	412,019
20R	27.46	1.00	1,620,000	-50,900	408,129
21R	27.50	0.89	1,710,000	-51,000	404,339
22R	27.50	0.89	1,597,000	-51,000	400,649
22L	27.50	0.89	1,490,000	-51,000	396,959
21L	27.50	0.89	1,368,000	-51,000	393,269
20L	27.46	1.00	1,113,000	-50,900	389,579
19L	27.38	1.25	808,000	-50,700	385,889
18L	27.30	1.53	593,000	-50,600	382,199
17L	27.22	1.70	472,500	-50,500	378,509
16L	27.10	2.23	314,000	-50,200	374,819
15L	26.98	2.85	209,500	-50,000	371,129
14L	26.84	3.69	134,200	-49,700	367,439
13L	26.65	4.90	80,250	-49,400	363,749
12L	26.42	6.87	42,500	-49,000	360,059
11L	26.16	9.79	19,690	-48,400	356,369
10L	25.87	14.14	6,740	-48,000	352,679
9L	25	19.96	-	-46,300	348,989
8L	22	17.10	-	-40,744	345,299
7L	19	14.29	-	-35,188	341,609
6L	16	11.86	-	-29,632	337,919
5L	13	9.76	-	-24,076	334,229
4L	10	7.32	-	-18,520	330,539
3L	7	5.80	-	-12,964	326,849
2L	4	4.51	-	- 7,408	323,159
1L	1	62.06	-	- 1,852	319,469

$$\Sigma = 19,559,970$$

$$H = \frac{19,559,970}{10547.52} = 1852$$

LIVE LOAD MOMENTS

Roadway width = 24'0"

Typical H-20 equivalent loading.

$$\text{Impact} = \frac{50}{L \sqrt{125}} = \frac{50}{206} = 24\%$$

$$\text{Load per sq. ft.} = \frac{640}{9} \times 1.24 = 88.3\%$$

$$\text{Excess concentration} = \frac{18000}{9} \times 1.24 = 2,430\%$$

In applying this loading the areas under the influence lines for the loaded length of the structure were determined and multiplied by the amount of the uniform load. To this was added the moment due to the effect of the excess concentration. In all cases, the load was placed so as to give the maximum conditions of loading.

Thrust factors NF, are V for points 2 to 8, and H for points 10 to 22. For point 9 it is the sum of the components of H and V at 45°.

The areas under the curves as well as the individual values of the curves at certain points are tabulated under the headings MF and NF. The areas under the curves are the summations of the values at the panel points so the product of MF and load per square foot must be multiplied by 3 to give correct results, since each center of division has the load from 3 lineal feet of bridge.

:	:	Point 2				:	Point 3				:							
:	:	MF	:	M	:	NF	:	N	:	MF	:	M	:	NF	:	N	:	
:	Load	:	:	:	:	:	:	:	:	:	:	:	:	:	:	:	:	
:	U.L.L.	:	-3342	:	-8853	:	13.50	:	3576	:	-59.26	:	-15,698	:	13.50	:	3576	:
:	C.L.L.	:	- 207	:	-5134	:	.50	:	1240	:	- 3.60	:	- 8,928	:	.50	:	1240	:
:	Total	:	:	:	-13987	:	:	:	4816	:	:	:	-24,626	:	:	:	4816	:
:	:	:	:	:	:	:	:	:	:	:	:	:	:	:	:	:	:	:
:	:	:	:	:	:	:	:	:	:	:	:	:	:	:	:	:	:	:
:	:	:	:	:	:	:	:	:	:	:	:	:	:	:	:	:	:	:

:	Point 4				:	Point 5				:
: Load	:MF	: M	: NF	: N	: MF	: M	: NF	: N	:	
: U.L.L.	-84.48	-22,379	13.50	3576	-109.94	-29,123	13.50	3576	:	
: C.L.L.	- 5.15	-12,772	.50	1240	- 6.70	-16,616	.50	1240	:	
:Total		-35,151		4816		-45,739		4816	:	
:									:	

: Load	Point 6					Point 7			
	: MF	: M	: NF	: N		: MF	: M	: NF	: N
: U.L.L.	: -135.10	: -35,788	: 13.50	: 3576		: -160.72	: -42,575	: 13.50	: 3576
: C.L.L.	: - 8.23	: -20,410	: .50	: 1240		: -9.78	: -24,254	: .50	: 1240
: Total		: -56,198		: 4816		: -66,829		: 4816	

: Load	Point 8					Point 9			
	: MF	: M	: NF	: N		: MF	: M	: NF	: N
: U.L.L.	: -186.16	: -49,314	: 13.50	: 3576		: -211.34	: -55,984	: 15.37	: 2240
: C.L.L.	: - 11.35	: -28,148	: .50	: 1240		: - 12.85	: -31,868	: .71	: 1754
: Total		: -77,462		: 4816		: -87,852		: 3994	

: Load	Point 10					Point 10			
	: MF	: M	: NF	: N		: MF	: M	: NF	: N
: U.L.L.	: -182.11	: -48,241	: 8.41	: 2227		: 1.50	: 397	: .05	: 13
: C.L.L.	: - 11.85	: -29,388	: .51	: 1265		: 1.50	: 3720	: .05	: 124
: Total		: -77,629		: 3492			: 4117		: 137

: Load	:	Point 11				:	Point 11				:
:	:	MF	M	NF	N	:	MF	M	NF	N	:
: U.L.L.	:	-151.77	-40,204	8.14	2158	:	/5.18	/1372	.52	85	:
: C.L.L.	:	-10.55	-26,164	.51	1265	:	/2.65	/6572	.11	273	:
			-66,368		3423			/7944		358	

: Load	:	Point 12				:	Point 12				:
:	:	MF	M	NF	N	:	MF	M	NF	N	:
: U.L.L.	:	-125.70	-33298	7.68	2035	:	/10.35	/2742	.78	206	:
: C.L.L.	:	- 9.35	-23138	.51	1265	:	/ 3.92	/9722	.16	397	:
			-56456		3300			/12464		603	

: Load	:	Point 13				:	Point 13				:
:	:	MF	M	NF	N	:	MF	M	NF	N	:
: U.L.L.	:	-102.84	-27,242	7.37	1953	:	/15.47	/4098	1.09	289	:
: C.L.L.	:	- 8.08	-20,038	.51	1265	:	/ 4.65	/11532	.21	521	:
			-47,280		3318			/15,630		810	

: Load	:	Point 14				:	Point 14				:
:	:	MF	M	NF	N	:	MF	M	NF	N	:
: U.L.L.	:	-82.77	-21,926	7.02	1860	:	/20.59	/5454	1.44	382	:
: C.L.L.	:	- 6.93	-17,186	.49	1215	:	/ 5.27	/13070	.26	645	:
			-39,112		3075			/18524		1027	

: Load	:	Point 15				:	Point 15				:
:	:	MF	M	NF	N	:	MF	M	NF	N	:
: U.L.L.	:	-65.18	-17266	6.20	1640	:	/ 25.76	/6824	2.26	600	:
: C.L.L.	:	- 5.80	-14384	.49	1215	:	/ 5.70	/14136	.31	769	:
			-31650		2855			/20960		1369	

: Load	Point 16				Point 16			
	MF	M	NF	N	MF	M	NF	N
: U.L.L.	-49.57	-13131	5.74	1520	/30.52	/8085	2.72	721
: C.L.L.	-4.78	-11706	.46	1140	/ 6.03	/15004	.35	869
		-24837		2660		/23089		1590

: Load	Point 17				Point 17			
	MF	M	NF	N	MF	M	NF	N
: U.L.L.	-36.29	-9613	5.25	1390	/33.57	/8893	3.21	850
: C.L.L.	- 3.68	-9126	.46	1140	/ 6.19	/15351	.39	968
		-18739		2530		/24244		1818

: Load	Point 18				Point 18			
	MF	M	NF	N	MF	M	NF	N
: U.L.L.	-24.49	-6487	4.75	1260	/36.43	/9650	3.71	985
: C.L.L.	- 2.78	-6746	.43	1067	/ 6.28	/15574	.43	1067
		-13233		2327		/23224		2052

: Load	Point 19				Point 19			
	MF	M	NF	N	MF	M	NF	N
: U.L.L.	-15.49	-4103	3.72	986	/38.25	/10,132	4.74	1260
: C.L.L.	- 1.93	-4786	.39	968	/ 6.27	/15,550	.46	1140
		-8889		1954		/25,682		2400

: Load	Point 20				Point 20			
	MF	M	NF	N	MF	M	NF	N
: U.L.L.	- 7.81	-2069	3.22	854	/39.65	/10503	5.24	1390
: C.L.L.	- 1.15	-2852	.35	869	/ 6.23	/15450	.49	1215
		-4921		1723		/25,953		2605

Point 21					Point 21				
Load	MF	M	NF	N	MF	M	NF	N	
U.L.L.	-2.43	-644	1.84	488	40.02	10601	6.62	1735	
C.L.L.	-.43	-1066	.26	645	6.17	15302	.51	1265	
		-1710		1133		25903		3020	

Point 22					Point 22				
Load:	MF	M	NF	N	MF	M	NF	N	
U.L.L.:-.22		-58	.54	143	40.54	10739	7.92	2100	
C.L.L.:-.10		-248	.11	273	6.13	15202	.51	1265	
		-306		416		23,941		3365	

SUMMARY OF MOMENTS AND THRUSTS

: Loading	: Point 2		: Point 3	
	: M	: N	: M	: N
: Dead	-43,776	38,848	- 79,512	37,198
: Earth Press. Rt.	/42,744	-1,429	/ 55,188	-1,429
: Earth Press. Lt.	- 7,408	-1,429	- 12,964	1,429
: Sub-total	-8,440	/38,848	- 37,288	/37,198
: Live /				
: Live -	-13,987	4,816	-24,626	4,816
: Temperature /	/ 576		/ 1,008	
: Temperature -	- 953		- 1,665	
: Max. Total -	-23,380	43,664	-63,579	42,014

: Loading	: Point 4		: Point 5	
	: M	: N	: M	: N
: Dead	-113,282	35,398	-147,420	33,448
: Earth Press. Rt.	/ 62,682	- 1,429	/ 65,946	- 1,429
: Earth Press. Lt.	- 18,520	1,429	- 24,076	1,429
: Sub-total	-69,120	/35,398	-105,550	33,448
: Live /				
: Live -	-35,151	4,816	-45,739	4,816
: Temperature /	/ 1,440		/ 1,873	
: Temperature -	- 2,380		- 3,095	
: Max. Total -	- 106,651	40,214	-154,364	38,264

: Loading	: Point 6		: Point 7	
	: M	: N	: M	: N
: Dead	-180,960	31,338	-215,540	29,078
: Earth Press. Rt.	/ 65,830	- 1,429	/ 63,154	-1,429
: Earth Press. Lt.	- 29,637	1,429	- 35,188	1,429
: Sub-total	-144,767	31,338	-187,574	29,078
: Live /				
: Live -	- 56,198	4,816	- 66,829	4,816
: Temperature /	/ 2,305		/ 2,735	
: Temperature -	- 3,810		- 4,525	
: Max. Totals -	- 204,770	36,154	-258,928	33,894

SUMMARY OF MOMENTS AND THRUSTS - Cont'd.

: Loading	Point 8		Point 9	
	M	N	M	N
: Dead	-249,870	27,673	-283,710	26,850
Earth Press. Rt.	/ 58,724	- 1,429	/ 53,310	300
: Earth Press. Lt.	- 40,744	1,429	- 46,300	2,330
Sub-total	-231,890	27,673	-276,700	28,480
: Live /				
: Live -	- 77,462	4,816	- 87,852	3,994
Temperature /	/ 3,170		/ 3,600	- 102
: Temperature -	- 5,240		- 5,960	/ 169
: Max. Total -	-314,592	32,489	-370,512	32,643

: Loading	Point 10		Point 11	
	M	N	M	N
: Dead	-231,592	11,334	-183,316	11,334
Earth Press. Rt.	/ 47,929	1,852	/ 43,839	1,852
: Earth Press. Lt.	-44,321	1,852	- 41,031	1,852
Sub-total	-227,984	15,038	-180,508	15,038
: Live /	/ 4,117	137	/ 7,944	358
: Live -	- 77,629	3,492	- 66,368	3,423
Temperature /	/ 3,730	144	/ 3,762	144
: Temperature -	- 6,160	238	- 6,230	238
: Max. Total -	-311,773	18,768	-253,106	18,699

: Loading	Point 12		Point 13	
	M	N	M	N
: Dead	-139,358	11,334	-102,369	11,334
Earth Press. Rt.	/ 39,549	1,852	/ 35,449	1,852
: Earth Press. Lt.	- 37,941	1,852	- 34,651	1,852
Sub-total	-137,750	15,038	-101,571	15,038
: Live /	/ 12,464	603	/ 15,630	810
: Live -	- 56,436	3,300	- 47,280	3,218
Temperature /	/ 3,810	144	/ 3,840	144
: Temperature -	- 6,290	238	- 6,350	238
: Max. Total -	-200,476	18,576	- 155,201	18,494

SUMMARY OF MOMENTS AND THRUSTS -Cont'd.

:Loading	:Point 14	:	:Point 15	:
:	: M	: N	: M	: N
:Dead	-69,925	11,334	-42,034	11,334
:Earth Press.Rt.	/31,469	1,852	/27,479	1,852
:Earth " Lt.	-31,261	1,852	-27,871	1,852
: Sub-total	-69,717	15,038	-42,426	15,038
:				
:Live /	/18,524	1,027	/20,960	1,369
:Live -	-39,112	3,075	-31,650	2,855
:Temperature /	/ 3,867	144	/ 3,885	144
:Temperature -	- 6,400	238	- 6,425	238
:Max. Total -	-115,229	18,351	-80,501	18,131

:Loading	:Point 16	:	:Point 17	:
:	: M	: N	: M	: N
:Dead	-19,770	11,334	/1511	11,334
:Earth Press.Rt.	/23,589	1,852	/19599	1,852
:Earth Press. Lt.	-24,381	1,852	-20991	1,852
: Sub-Total	-20,562	15038	/119	15038
:				
:Live /	/23089	1,590	/24,244	1818
:Live -	-24837	2,660	-18,739	2530
:Temperature /	/ 3905	144	/ 3,920	144
:Temperature -	- 6450	238	- 6,490	238
:	/ 6,432	16,772	/28,283	17,000
: Max.Total -	-51,849	17,938	-25,110	17,806

:Loading	:Point 18	:	:Point 19	:
:	: M	: N	: M	: N
:Dead	/16,899	11,334	/28,271	11,334
:Earth Press. Rt.	/15,809	1,852	/12,019	1,852
:Earth Press. Lt.	-17,401	1,852	-13,811	1,852
: Sub-Total	/15,307	15,038	/26,479	15,038
:				
:Live /	/25,284	2,052	/25,682	2,400
:Live -	-13,233	2,327	- 8,889	1,954
:Temperature /	/ 3,935	144	/3,942	144
:Temperature -	- 6,510	238	-6,520	238
:	/44,466	17,234	/56,103	17,582
: Max. Total	- 4,436	17,603		

SUMMARY OF MOMENTS AND THRUSTS - Cont'd.

Loading	Point 20		Point 21	
	M	N	M	N
Dead	36,032	11,334	44077	11,334
Earth Press. Rt.	8,129	1,852	4339	1,852
Earth Press. Lt.	10,321	1,852	6731	1,852
Sub-total	33,840	15,038	41685	15,038
Live	25,963	2,605	25903	3,020
Live -	4,921	1,723	1710	1,133
Temperature	3,958	144	3962	144
Temperature -	6,540	238	6550	238
	63,761	17,787	71550	18,202
Max. Total -				


Loading	Point 22	
	M	N
Dead	46,826	11,334
Earth Press. Rt.	649	1,852
Earth Press. Lt.	3,041	1,852
Sub-total	44,434	15,038
Live	25,941	3,565
Live -	306	416
Temperature	3,962	144
Temperature -	6,550	238
	74,337	18,547
Max. Total -		

DESIGN OF SECTIONS

[illegible]


DESIGN OF SECTIONS

Point	$\frac{e'}{d}$	$K = \frac{N e'}{b d^2}$	f_c Pounds Per Sq.In.	f_s Pounds Per S. In.	Required P	Required As Sq.Ins. Per Ft. Width	Point
2	.63	54.6	490	18000			2
3	.87	66.2	550	18000			3
4	1.11	74.5	590	18000	.0009	.54	4
5	1.37	80.5	620	18000	.0017	1.11	5
6	1.65	85.4	640	18000	.0024	1.68	6
7	1.96	88.9	660	18000	.0030	2.24	7
8	2.23	91.1	660	18000	.0032	2.52	8
9	2.43	94.5	680	18000	.0037	3.11	9
10	3.76	94.9	680	18000	.0044	3.28	10
11	3.44	97.5	700	18000	.0048	3.17	11
12	3.21	102.5	710	18000	.0044	2.56	12
13	2.82	101.0	710	18000	.0042	2.17	13
14	2.40	95.4	680	18000	.0037	1.71	14
15	2.28	98.5	700	18000	.0039	1.64	15
16	1.55	72.4	575	18000	.0018	.69	16
16	.61	26.6	330	18000	-	-	16
17	1.05	83.7	725	18000	.0010	.35	17
17	1.15	86.2	500	18000	.0007	.25	17
18	.58	31.5	350	18000	-	-	18
18	2.34	124.5	800	17500	.0050	1.62	18
19	1.99	116.5	780	18000	.0040	1.20	19
20	2.33	150.0	800	12000	.0090	2.48	20
21	2.60	179.3	800	8000	.0181	4.78	21
22	2.64	185.8	800	7000	.0210	5.30	22



GENERAL NOTES

Loading: Typical H-20 Impact Allowed.
 Concrete: 1-2-3½ mix. Maximum size of aggregate, ½"
 Reinforcing of steel bars
 Chamfer all exposed edges ¾", unless noted.
 Back face of vertical legs spade finish.
 Other parts rubbed finish.









GA. SCHOOL OF TECHNOLOGY

PLAN AND ELEVATION
 RIGID FRAME BRIDGE

Scale: 1" = 8'-0"

June 1932



GA. SCHOOL OF TECHNOLOGY

DETAILS OF RIGID FRAME BRIDGE

Scale: $\frac{3}{16}'' = 1'-0''$

June 1932

EXPERIMENTATION

EXPERIMENTATION

As mentioned before, the rigid frame bridge is no longer a mere experiment. Before the practicability of its design could be assured many tests were carried out. The Westchester County Park Commission instigated a great number of these tests and the results have influenced the development of the design greatly.

Probably the first question to be raised by those who were skeptical as to the safety of the type was the problem of the stress conditions around the knee, that is, around the bend at the juncture of the vertical leg and the rib proper. In answer to the question, a number of laboratory tests were made on right angled knees of reinforced concrete. It was found that the detail had sufficient safety but also that a peculiar situation existed. The greater the load that was applied the closer the neutral axis in the concrete approached the inside of the knee. As can be seen, this would call for an extremely high compression in the concrete - in fact, one that would be prohibitive. This peculiar location of the axis was verified by photo-elastic analysis also. There remained then the task of correlating these two facts; that the detail was safe, and that very high compressive stresses were produced. The explanation of this, however, is that the compressive stress which concrete can be depended upon to carry is a great deal higher if the pressure comes from all sides at once. In other words, the concrete at the knee of the rigid frame is subjected to a confined stress. In ordinary compression tests on concrete specimens, the failure is always due to shearing off of the specimen on an inclined plane. If this specimen were compressed

on all faces with equal forces a very high compressive stress would be indicated. Some bridges have been constructed using filleted knee joints in an attempt to move the neutral axis farther from the compressive face, but since the unfilleted knees have proven their safety and their appearance is more pleasing, the fillets are not used very often.

The deformer method of analyzing the behavior of highly indeterminate structures has yielded very gratifying results. The procedure is to construct a flat model of the structure from some elastic material, making the depth of any section in proportion to the cube root of the gross moment of inertia of the corresponding section of the original structure. Then deflections of known magnitude are caused at one section of the structure and the relative deflection at other sections studied. When the proper apparatus is available this method is extremely satisfactory and results can be obtained in close agreement with the laborious mathematical results, at a great saving in time and trouble. Filar micrometer microscopes are necessary as well as specially constructed plugs and plug bars for causing deflections. It should be noticed that, in all cases, the gross moment of inertia is used. The reason for this is that the theory of the design depends on the flexure in the structure and the flexure is caused by the action of the whole cross-section and not by occasional sections where the moment of inertia is less. Applied to a reinforced concrete bridge this means that the flexure is caused, not by an occasional cracked section, but by the flexure due to tension and compression of the whole cross-section.

Two concrete models were constructed by the Bronx Parkway

Commission and loaded to destruction. The safety of the design was proven by the fact that stresses of 79000 and 4900 lbs. per sq. in. in steel and concrete, respectively, were calculated at the point of failure. The failure occurred at the center of the crown since the applied load was concentrated at that point. An additional factor of safety was noticed in these field models that is both interesting and valuable. Upon failure of the concrete in compression at the crown, the structure did not fall but continued to support the load acting then as two half arches, hinged at the crown by the action of the steel at that point. This additional factor of safety, it can easily be seen, is most desirable and is a characteristic not possessed by the simple beam type of bridges.

The model constructed by the writer was designed as a free end rigid frame. It has a clear span of 9'-4" and a height of approximately 6'-0" from bottom of footings to top of rib. It was designed to carry live loads of 1000 lbs. at center of span and 1000 lbs. at points 3 ft. on each side of the center. These loads were arbitrarily assumed since it was thought that these conditions could be realized with the facilities available for loading the bridge. Several pictures made of the bridge during and after construction are included. The model was made with a width of 1 ft. since the tests could be made on a 1 ft. wide model as well as on a wider one.

A hole approximately 5 ft. wide, 12 ft. long and 5 ft. deep was dug in which to construct the bridge. This was done for two reasons; first, to permit easy placing of the approach fills on the ends of the bridge; and second, to facilitate pouring the concrete without the use of a

ramp or other such device. The earth at the ends of the structure was dug back approximately 5 ft. at both ends so that the earth could be backfilled and actual structural conditions simulated.

The next problem was that of devising a method of loading the bridge. To do this it was decided to construct the bridge with two 4"x6" timbers running under the footings from one footing to the other. Under these timbers, at the midpoints, and at 3' each side of the midpoint, 3/4" ϕ cables of sufficient length to form a loop over the top of the rib were placed. The two ends of the cable could be clamped together forming a continuous loop under the timbers and over the bridge. A jack-type lodometer was to be used between the cable and the top of the rib. Then when the jack was used against the cable it was equivalent to a load being applied to the bridge, and the amount of the load could be determined. Fig. 10 shows a sketch of this arrangement.

Strain gauge measurements were to be taken with telemeters so it was necessary to place telemeter plugs at the desired points in the bridge. This is accomplished by screwing the plugs to spacer bars, or templates, at the required distance apart and fastening the spacer bar into the face of the form at the spot where measurements are desired. Seven sets of telemeter plugs were used on the model. The placing of these plugs is shown in Fig. 11. It can be noticed that two sets were used at the knee on one side of the bridge. This was to measure the relative stresses at two points in order to determine the position of the neutral axis at the knee.

The conditions of the footings caused by the use of piles is somewhat a matter of speculation. Of course, complete fixity as in the case of anchorage to rock cannot be assumed but some fixity does occur.







FIGURE 10



PLACING OF TELEMETERS

FIGURE 11.

The amount of this restraint and its effect on the stresses being problematical, it was desired to make an attempt to determine whether restraint from timber could be assumed. The fact that timber is more flexible, having a lower modulus of elasticity, makes it a matter of question whether or not the footing is allowed to deflect before the calculated moment necessary for restraint is developed. A 4"x6" timber about 7 ft. long was placed under each footing extending about 5 ft. back under the approach fills. A plate was placed under this timber, thru which 2- 5/8" ϕ bolts extended up thru the footing. A set of tests could then be run with the bolts free, the bond having been kept from the bolts by using tin cylinders around them. Then by screwing nuts on the bolts down tight the timbers exert a restraining moment and another set of tests could be run and the results compared. This can also be seen in Fig.10.

The bridge model was poured in the same order as one of larger proportions would be poured. The footings were poured as the first operation; key joints being made at their tops. Then the vertical legs were constructed with the tops stepped off as shown on the details of the model. Then the top of the frame forms the last operation.

The complete design, including all calculations relative to the bridge model are included. The procedure is similar to that shown previously for the 81'-0" frame. It may be noticed that reinforcing was placed in the soffit fibers of the vertical legs, although no tension was calculated at this point under the design assumptions used. However, if the partial restraint at the footings




*Vertical Leg Before Removing Forms.
Notice bolts projecting from footings.*



Model After Forms Were Removed.

were realized this steel would be necessary. Experience has shown that the moment at the footings is developed in such a direction as to cause positive moment just above the footings. Also, nominal reinforcing was deemed advisable in the footings, placed so as to resist any tendency of the footings to crack off due to this restraining moment. Stirrups could have been used as an additional safety precaution in the top slab of the frame but were omitted because of the fact that difficulty would have been caused in pouring the concrete. As it was, the small dimensions of the model and the closeness of the reinforcing made the tamping of the concrete without disturbing the bars extremely difficult.



GA. SCHOOL OF TECHNOLOGY

DESIGN OF RIGID FRAME MODEL

[illegible]

$$\sum \frac{Y^2}{I} \text{ for full span } = 8 \times 25,789 = 206,312$$

INFLUENCE LOAD = 10.

:Pt. :	Influence Load at 7 R				:
	Mom. :	$\frac{M_y}{I}$:	R_y :	Total :	
:	:	I :	I :	Mom. :	:
: 1L :	0	0	- .27	- .27:	:
: 2L :	0	0	-1.09	-1.09:	:
: 3L :	0	0	-1.91	-1.91:	:
: 4L :	0	0	-2.73	-2.73:	:
: 5L :	0	0	-3.55	-3.55:	:
: 6L :	0	0	-4.34	-4.34:	:
: 7L :	1	249.8	-4.53	-3.53:	:
: 8L :	2	1166.6	-4.59	-2.59:	:
: 9L :	3	3133.2	-4.62	-1.62:	:
: 10L :	4	5958.0	-4.64	- .64:	:
: 11 :	5	8859.5	-4.65	1.35:	:
: 10R :	6	8937.0	-4.64	1.36:	:
: 9R :	7	7310.8	-4.62	2.38:	:
: 8R :	8	4666.4	-4.59	3.41:	:
: 7R :	9	2248.2	-4.53	4.47:	:
: 6R :	0	0	-4.34	-4.34:	:
: 5R :	0	0	-3.55	-3.55:	:
: 4R :	0	0	-2.73	-2.73:	:
: 3R :	0	0	-1.91	-1.91:	:
: 2R :	0	0	-1.09	-1.09:	:
: 1R :	0	0	- .27	- .27:	:

$$\Sigma = 42,589.5$$

$$H = \frac{42,589.5}{\frac{y^2}{I}} = .82$$

INFLUENCE LOAD = 10

Pt.	Influence Load at 8R			
	Mom.	My I	Hy	Total Mom.
1L	0	0	-.53	-.53
2L	0	0	-2.13	-2.13
3L	0	0	-3.73	-3.73
4L	0	0	-5.33	-5.33
5L	0	0	-6.93	-6.93
6L	0	0	-8.46	-8.46
7L	2	499.6	-8.83	-8.83
8L	4	2333.2	-8.96	-4.96
9L	6	6266.4	-9.02	-3.02
10L	8	11916.0	-9.06	-1.06
11	10	17719.0	-9.07	/.93
10R	12	17874.0	-9.06	/2.94
9R	14	14621.6	-9.02	/4.98
8R	16	9332.8	-8.96	/7.04
7R	8	1998.4	-8.83	-.83
6R	0	0	-8.46	-8.46
5R	0	0	-6.93	-6.93
4R	0	0	-5.33	-5.33
3R	0	0	-3.73	-3.73
2R	0	0	-2.13	-2.13
1R	0	0	-.53	-.53

$$\Sigma = 82561.0$$

$$H = \frac{82561}{51,578} = 1.60$$

INFLUENCE LOAD = 10

:Pt. :	Influence Load at 9R				:
	Mom.	$\frac{My}{I}$	Hy	Total Mom.	
: 1L	0	0	- .75	- .75	:
: 2L	0	0	-3.01	- 3.01	:
: 3L	0	0	-5.27	- 5.27	:
: 4L	0	0	-7.53	- 7.53	:
: 5L	0	0	-9.79	- 9.79	:
: 6L	0	0	-11.96	- 11.96	:
: 7L	3	749.4	-12.48	- 9.48	:
: 8L	6	3499.8	-12.66	- 6.66	:
: 9L	9	9399.6	-12.75	- 3.75	:
: 10L	12	17874.0	-12.79	- .79	:
: 11	15	26578.5	-12.81	/ 2.19	:
: 10R	18	26811.0	-12.79	/ 5.21	:
: 9R	21	21932.4	-12.75	/ 8.25	:
: 8R	14	8166.2	-12.66	/ 1.34	:
: 7R	7	1748.6	-12.48	- 5.48	:
: 6R	0	0	-11.96	- 11.96	:
: 5R	0	0	- 9.79	- 9.79	:
: 4R	0	0	- 7.53	- 7.53	:
: 3R	0	0	- 5.27	- 5.27	:
: 2R	0	0	- 3.01	- 3.01	:
: 1R	0	0	- .75	- .75	:
:					:
:					:
:					:

$$\Sigma = 116,759.5$$

$$H = \frac{116,759.5}{51,678} = 2.26$$

INFLUENCE LOAD = 10

: Point :	Influence Load at 10R				:
:	Mom.	My	Hy	Total	:
:	:	I	:	Mom.	:
1L	0	0	- .90	- .90	:
: 2L	0	0	- 3.62	- 3.62	:
3L	0	0	- 6.34	- 6.34	:
: 4L	0	0	- 9.06	- 9.06	:
5L	0	0	-11.78	-11.78	:
: 6L	0	0	-14.39	-14.39	:
7L	4	999.2	-15.01	-11.01	:
: 8L	8	4666.4	-15.23	- 7.23	:
9L	12	12322.8	-15.34	- 3.34	:
: 10L	16	23832.0	-15.40	✓ .60	:
11	20	35438.0	-15.42	✓ 4.58	:
: 10R	24	35748.0	-15.40	✓ 8.60	:
9R	18	18784.2	-15.34	✓ 2.66	:
: 8R	12	6999.6	-15.23	- 3.23	:
7R	8	1498.8	-15.01	- 9.01	:
: 6R	0	0	-14.39	-14.39	:
5R	0	0	-11.78	-11.78	:
: 4R	0	0	- 9.06	- 9.06	:
3R	0	0	- 6.34	- 6.34	:
: 2R	0	0	- 3.62	- 3.62	:
1R	0	0	- .90	- .90	:
:					:
:					:
:					:
:					:

$\Sigma = 140489.0$


$$H = \frac{140,489}{51,578} = 2.72$$


Influence Load = 10

INFLUENCE LOAD AT 11				
Pt.	Mom.	$\frac{My}{I}$	Hy	Total M
1 L	0	0	- .96	- .96
2 L	0	0	-3.86	-3.86
3 L	0	0	-6.76	-6.76
4 L	0	0	-9.66	-9.66
5 L	0	0	-12.56	-12.56
6 L	0	0	-15.34	-15.34
7 L	5	1249.0	-16.01	-11.01
8 L	10	5833.0	-16.24	- 6.24
9 L	15	15666.0	-16.36	- 1.36
10 L	20	29790.0	-16.41	✓ 3.59
11	25	44297.5	-16.44	✓ 8.56
10 R	20	29790.0	-16.41	✓ 3.59
9 R	15	15666.0	-16.36	- 1.36
8 R	10	5833.0	-16.24	- 6.24
7 R	5	1249.0	-16.01	-11.01
6 R	0	0	-15.34	-15.34
5 R	0	0	-12.56	-12.56
4 R	0	0	- 9.66	- 9.66
3 R	0	0	- 6.76	- 6.76
2 R	0	0	- 3.86	- 3.86
1 R	0	0	- .96	- .96

$$\Sigma = 96835.5$$

$$H = \frac{96,835.5}{51,578} = 2.90$$





RIGID FRAME MODEL

DEAD LOAD MOMENTS

: Load :		: Point 2 :		: Point 3 :		: Point 4 :		: Point 5 :		: Point 6 :	
: Pt. :	: Load :	: MF :	: M :	: MF :	: M :	: MF :	: M :	: MF :	: M :	: MF :	: M :
7L	100	-.109	-10.9	-.191	-19.1	-.273	-27.3	-.355	-35.5	-.434	-43.4
8L	75	-.213	-15.98	-.373	-27.98	-.533	-39.98	-.693	-51.98	-.846	-63.45
9L	60	-.301	-18.06	-.527	-31.62	-.753	-45.18	-.979	-58.74	-1.196	-71.76
10L	55	-.362	-19.91	-.634	-34.87	-.906	-49.83	-1.178	-64.79	-1.439	-79.15
11	50	-.386	-19.30	-.676	-33.80	-.966	-48.30	-1.256	-62.80	-1.534	-76.70
10R	55	-.362	-19.91	-.634	-34.87	-.906	-49.83	-1.178	-64.80	-1.439	-79.15
9R	60	-.301	-18.06	-.527	-31.62	-.753	-45.18	-.979	-58.74	-1.196	-71.76
8R	75	-.213	-15.98	-.373	-27.98	-.533	-39.98	-.693	-51.98	-.846	-63.45
7R	100	-.109	-10.9	-.191	-19.1	-.273	-27.3	-.355	-35.5	-.434	-43.4
Totals-			-149.00		-261.04		-372.88		-484.82		-592.22

: Id. : Load :		: Point 7 :		: Point 8 :		: Point 9 :		: Point 10 :		: Point 11 :	
: Pt. :	: Load :	: MF :	: M :	: MF :	: M :	: MF :	: M :	: MF :	: M :	: MF :	: M :
7L	100	/.447	/44.7	/.341	/34.1	/.238	/23.8	/.136	/13.6	/.035	/3.5
8L	75	-.083	-6.23	/.704	/52.80	/.498	/37.35	/.294	/22.05	/.093	/6.98
9L	60	-.548	-32.88	/.134	/8.04	/.825	/49.50	/.521	/31.26	/.219	/13.14
10L	55	-.901	-49.56	-.323	-17.17	/.866	/14.63	/.860	/47.30	/.458	/25.19
11	50	-1.101	-55.05	-.624	-31.20	-.136	-6.80	/.359	/17.95	/.856	/42.80
10R	55	-1.101	-60.56	-.723	-39.77	-.334	-18.37	/.060	/3.30	/.458	/25.19
9R	60	-.948	-56.88	-.666	-39.96	-.375	-22.50	-.079	-4.74	/.219	/13.14
8R	75	-.683	-51.23	-.496	-37.20	-.302	-22.65	-.106	-7.95	/.093	/6.98
7R	100	-.353	-35.3	-.259	-25.9	-.162	-16.2	-.064	-6.4	/.035	/3.5
			-302.99		-96.86		/38.76		/116.37		/140.42

D.L. NORMAL THRUSTS

V.R. = 1060#

Point 1 N = 1060

2 835

3 755

4 665

5 565

6 (450x0.71)/(112x.71) = 400

Point 7 = 112

8 112

9 112

10 112

11 112

RIGID FRAME MODEL

Temperature Stresses

$$e = .0000065$$

$$t = +45 \text{ or } -35$$

$$E = 2,000,000 \times 144 = 288,000,000 \text{ lbs./sq. ft.}$$

$$S = 1.0$$

$$H = \frac{E_c t l}{S \sum \frac{y^2}{I}} = \frac{842,400}{51,578} = +16.3$$

$$H = - \frac{35}{45} \times 16.3 = -12.7$$

Point:	y :	H _y	-H _y	:
2	1.33	21.69	-16.89	:
3	2.33	37.98	-28.59	:
4	3.33	54.28	-42.29	:
5	4.33	70.58	-54.99	:
6	5.29	86.23	-67.18	:
7	5.52	89.98	-70.10	:
8	5.60	91.28	-71.12	:
9	5.64	91.93	-71.63	:
10	5.66	92.26	-71.88	:
11	5.67	92.42	-72.01	:
:	:	:	:	:
:	:	:	:	:

Points 2 to 4, N = 0

Point 5

$$+N = .71 \times 16.3 = +11.6$$

$$-N = .71 \times 12.7 = -9.0$$

Points 6 to 11

$$+N = +H = +16.3$$

$$-N = -H = -12.7$$

RIGID FRAME MODEL

RIB SHORTENING

Point	N	t	f_o #/sq. ft	Δx	$f_o \Delta x$
2	5835	.52	11,221	0	-
3	5755	.604	9,528	0	-
4	5665	.687	8,246	0	-
5	5565	.740	7,322	0	-
6	5167	.833	6,203	0	-
7	1826	.625	2,922	1	2922
8	1826	.479	3,812	2	7624
9	1826	.396	4,611	3	13833
10	1826	.354	5,158	4	20632
11	1826	.333	5,483	5	13708

$$\Sigma = 58719$$

$$f_o \Delta x \text{ for full span} = 2 \times 58719 = 117,438$$


$$H = \frac{-\Sigma f_o \Delta x}{\Sigma \frac{y^2}{I}} = - \frac{117,438}{51,578} = -2.28$$

Point	y	Hy
2	1.33	- 3.03
3	2.33	5.31
4	3.33	7.59
5	4.33	9.87
6	5.29	12.06
7	5.52	12.59
8	5.60	12.77
9	5.64	12.86
10	5.66	12.90
11	5.67	12.93

As can be seen, these values are negligible, so were ignored.

RIGID FRAME MODEL

Earth Pressure-Right



$$V_L = V_R = \frac{481.0 \times 1.91}{10} = 91.85$$

Assume earth pressure =
30#/ sq.ft. (fluid)

Point	Vertical Distance from 0	Vertical Distance Between	Earth Press. Rt. Loads	Sum of Loads	Inc. of Mom	Partial Mom A	Hor. Dist. From 0=X	Mom B = Vx	Sub-Total M _a /M _b
HL	0	.167	481.0	481.0	80.3		0	0	0
E1	.167	.167	55.0	426.0	71.0	80.3			
1R	.33	.50	-	426.0	213.0	151.3			151.3
E2	.83	.50	145.0	281.0	140.5	364.3			
2R	1.33	.50	-	281.0	140.5	504.8			504.8
E3	1.83	.50	115.0	166.0	83.0	645.3			
3R	2.33	.50	-	166.0	83.0	728.3			728.3
E4	2.83	.50	85.0	81.0	40.5	811.3			
4R	3.33	.50	-	81.0	40.5	851.8			851.8
E5	3.83	.50	55.0	26.0	13.0	892.3			
5R	4.33	.48	-	26.0	12.5	905.3			905.3
E6	4.81	.48	24.7	1.3	0.6	917.8			
6R	5.29	.11	-	1.3	0.1	918.4			918.4
E7	5.40	.12	1.3	0.0	0.0	918.5			
7R	5.52	.08	-			918.5	1	-91.8	826.7
8R	5.60	.04	-			918.5	2	-183.7	734.8
9R	5.64	.02	-			918.5	3	-275.5	643.0
10R	5.66	.01	-			918.5	4	-367.4	551.1
11	5.67		-			918.5	5	-459.2	459.3
10L	5.66		-			918.5	6	-551.1	367.4
9L	5.64		-			918.5	7	-642.9	275.6
8L	5.60		-			918.5	8	-734.8	183.7
7L	5.52		-			918.5	9	-826.6	91.9
6L	5.29		-			918.5	10	-918.5	0
5L	4.33		-			918.5	10	-918.5	0
4L	3.33		-			918.5	10	-918.5	0
3L	2.33		-			918.5	10	-918.5	0
2L	1.33		-			918.5	10	-918.5	0
1L	.33		-			918.5	10	-918.5	0

: Point : Y : I : $\frac{M_y}{I}$: H_y : Total Mom:						RIGID FRAME MODEL
: : : : : : $\frac{M_x}{M_0}, \frac{H_y}{H_0}$:						Earth Pressure-Right
: : : : : :						
						(Cont)
: HL	0					
E1						
: 1R	33	.5302	/94	-27.8	/123.5	
E2						
: 2R	1.33	.0122	/55023	-111.9	/392.9	
E3						
: 3R	2.33	.0197	/86158	-196.0	/532.3	
E4						
: 4R	3.33	.0290	/97767	-280.1	/571.7	Normal Thrusts:
E5						6R=(84.1-91.85).71= -5.5
: 5R	4.33	.0399	/98285	-364.2	/541.1	
E6						
: 6R	5.29	.0525	/92575	-444.9	/473.5	6L=(84.1/91.85).71=/124.9
E7						
: 7R	5.52	.0221	/206675	-464.2	/362.5	2R to 5R
8R	5.60	.0096	/428509	-471.0	/263.8	N = -91.85
: 9R	5.64	.0054	/671549	-474.3	/168.7	2L to 5L
10R	5.66	.0038	/820808	-476.0	/ 75.1	N = /91.85
: 11	5.67	.0032	/813834	-476.8	- 17.5	
10L	5.66	.0038	/547206	-476.0	-108.6	7R to 7L
: 9L	5.64	.0054	/287837	-474.3	-198.7	N = 84.1
8L	5.60	.0096	/107152	-471.0	-287.3	
: 7L	5.52	.0221	/22975	-464.2	-372.3	
6L	5.29	.0525	0	-444.9	-444.9	
: 5L	4.33	.0399	0	-364.2	-364.2	
4L	3.33	.0290	0	-280.1	-280.1	
: 3L	2.33	.0197	0	-196.0	-196.0	
2L	1.33	.0122	0	-111.9	-111.9	
: 1L	.33	.5302	0	-27.8	- 27.8	

$\Sigma = 4338387$

$$H = \frac{4338387}{51,578} = 84.1$$

RIGID FRAME MODEL

LIVE LOAD MOMENTS

: Load	: Load	: Point 2	: Point 3	: Point 4	: Point 5				
: Point	: Lbs.	: MF	: M	: MF	: M	: MF	: M	: MF	: M
: 8L	1000	-.213	-213	-.373	-373	-.533	-533	-.963	-693
: 11	1000	-.386	-386	-.676	-676	-.966	-966	-1.256	-1256
: 8R	1000	-.213	-213	-.373	-373	-.533	-533	-.693	-693
: Totals -			-812		-1422		-2032		-2642

: Load	: Load	: Point 6	: Point 7	: Point 8	: Point 9				
: Point	: Lbs.	: MF	: M	: MF	: M	: MF	: M	: MF	: M
: 8L	1000	-.846	-846	-.083	-83	/.704	/704	/.498	/498
: 11	1000	-1.534	-1534	-1.101	-1101	-.624	-624	-.136	-136
: 8R	1000	-.846	-846	-.683	-683	-496	-496	-.302	-302
: Totals -			-3224		-1867		/704		/498
							-1120		-438

: Load	: Load	: Point 10	: Point 11		
: Point	: Lbs.	: MF	: M	: MF	: M
: 8L	1000	/.294	/294	/.093	/93
: 11	1000	/.359	/359	/.856	/856
: 8R	1000	-.106	-106	/.093	/93
: Totals-			/653		/1042
			-106		

L.L. Normal Thrusts

V.R = 1500#

Point 1- N = 1500
 2 = 1500
 3 = 1500
 4 = 1500
 5 = 1500
 6 = $(0.71 \times 1500) / (0.71 \times 610) = 1500$
 7 = 610
 8 = 610
 9 = 610
 10 = 610
 11 = 610

RIGID FRAME MODEL

SUMMARY OF MAXIMUM MOMENTS
AND NORMAL THRUSTS

	Point 2		Point 3		Point 4	
Loading	M	N	M	N	M	N
Dead	-149.0	835	-261.0	755	-372.9	665
Earth P.-Rt.	-111.9	- 92	-196.0	- 92	- 280.1	- 92
Earth P. Lt.	/392.9	/ 92	/532.3	/ 92	/571.7	/ 92
Sub-total	/132.0	835	/75.0	755	- 81.3	665
-Live	-812.0		-1422.0		-2032.0	
/Live		1500		1500		1500
-Temp.	-16.9		-29.6		- 42.3	
/Temp.	/21.7		/38.0		/ 54.3	
	-696.9	2335	-1576.6	2255	-2155.6	
MAX.TOTAL	/153.7	835	/113.0	/ 755		/2165

	Point 5		Point 6		Point 7	
Loading	M	N	M	N	M	N
Dead	-484.8	565	-592.2	40.0	-303.0	/112
Earth P.-Rt.	-364.2	-92	-444.9	- 6	-372.3	/ 84
Earth Pr. Lt.	/541.1	/92	/473.5	/125	/362.5	/84
Sub-total	-307.9	565	-563.6	519	-312.8	280
-Live	-2642.0		-3224.0		-1867.0	
/Live		1500		1500		610
-Temp.	-55.0		-67.2	- 10	- 70.1	-13
/Temp.	/70.6		/86.2	/ 12	/ 90.0	/16
	-3004.9		-3854.8		-2249.9	
Max.Total		/2065		/2009		/877

RIGID FRAME MODEL
SUMMARY OF MAXIMUM MOMENTS
AND NORMAL THRUSTS



	Point 8		Point 9		Point 10		POINT 11	
: Loading	: M	: N	: M	: N	: M	: N	: M	: N
: Dead	:-96.9	: 112	: 36.8	: 112	: 116.4	: 112	: 140.4	: 112
: Earth P.-Rt.	:-287.3	: 84	: 198.7	: 84	:- 108.6	: 84	:- 17.5	: 84
: Earth P.-Lt.	: 283.8	: 84	: 168.7	: 84	: 75.1	: 84	:- 17.5	: 84
:	:	:	:	:	:	:	:	:
: Sub-total	:-120.4	: 280	: 8.8	: 280	: 82.9	: 280	: 105.4	: 280
: -Live	:-180.0	: 450	:-438.0	: 450	:- 106.0	: 160	:	:
: /Live	: 704.0	: 160	: 498.0	: 160	: 653.0	: 450	: 4042.0	: 610
: -Temp.	:- 71.1	: 13	:- 71.6	: 13	:- 71.9	: 13	: -72.0	: 13
: /Temp.	: 91.3	: 16	: 91.9	: 16	: 92.3	: 16	: 92.4	: 16
:	:	:	:	:	:	:	:	:
:	:-1311.5	: 717	:-500.8	: 717	:- 95.0	: 427	:	:
: Max. Total -	: 674.9	: 456	: 598.7	: 456	: 828.2	: 746	: 123.8	: 906

DESIGN OF SECTIONS

Pt.	Foot	Inch	Lbs.	M+N	Inches	t-1.5"	e/t-1.5"	e'	K _c
	pounds	Pounds			Inches			$\frac{Ne'}{bd^2}$	
2	-696.9	-8363	2335	358	6.25	4.75	5.21	1.10	54.1
2	/153.7	/1845	835	2.21	6.25	4.75	3.84	.81	11.9
3	-1376.6	-16520	2255	7.33	7.25	5.75	9.46	1.65	53.9
3	/113.0	/1356	755	1.80	7.25	5.75	3.93	.69	7.6
4	-2155.6	-25868	2165	11.93	8.13	6.63	14.50	2.19	59.6
5	-3004.9	-36059	2065	17.45	9.13	7.63	20.52	2.69	60.7
6	-3854.9	-46259	2009	22.10	10.00	8.50	25.60	3.01	59.4
7	-2249.9	-27000	877	30.78	7.50	6.00	33.03	5.50	67.0
8	-1311.5	-15738	717	21.95	5.75	4.25	23.335	5.0	77.3
8	/674.9	/8099	456	17.75	5.75	4.25	19.13	5.50	40.3
9	-500.8	-6010	717	8.39	4.75	3.25	9.26	5.50	38.3
9	/598.7	/7185	456	15.75	4.75	3.25	16.63	4.50	59.8
10	-95.0	-1140	427	2.67	4.25	2.75	3.30	2.85	15.5
10	/828.2	/9939	746	13.30	4.25	2.75	13.93	5.12	114.5
11	/1239.8	/14878	906	16.40	4.25	2.75	17.03	1.20	169.9

Point	f _c -pounds	f _s -pounds	Req'd	Req'd.	Bars to be
	per sq.	per sq.	p	As Sq.	Used
	inch	inch		In.	
2(-)	430	16000	.0007	.040	1-1/4" ϕ -
2(/)					
3(-)	430	16000	.0017	.117	3-1/4" ϕ 's
3(/)					
4	450	16000	.0025	.199	1-3/8" ϕ - 2-1/4" ϕ 's
5	460	16000	.0028	.256	2-3/8" ϕ 's 2-1/4" ϕ 's
6	450	16000	.0029	.296	2-3/8" ϕ 's 2-1/4" ϕ 's
7	490	16000	.0039	.281	2-3/8" ϕ 's 2-1/4" ϕ 's
8(-)	530	16000	.0045	.227	2-3/8" ϕ 's 1-1/4" ϕ 's
8(/)	350	16000	.0022	.112	3-1/4" ϕ 's
9(-)	350	16000	.0018	.070	1-3/8" ϕ 1-1/4" ϕ
9(/)	450	16000	.0034	.133	3-1/4" ϕ 's
10(-)					
10 /	675	16000	.0068	.224	1-5/8" ϕ 2-3/8" ϕ 's
11 /	800	11200	.0157	.518	1-5/8" ϕ 2-3/8" ϕ 's

These computations were made in this manner so as to be able to use diagram for bending and direct stress from Hool and Johnson's Concrete Engineer's Handbook. Steel in compressive face ignored.



GENERAL NOTES

Concrete: 1-2-3½ mix. Maximum size aggregate, 1".

Reinforcing of steel bars.

Cover on steel, $1\frac{1}{2}$ " unless noted.

Telemeter plugs and Level bar plugs to be placed in concrete as called for on special sketch.

Suitable timber bulkheads to be provided at both ends of bridge and approach fills placed in 1 ft. layers up to top of rib.

GA. SCHOOL OF TECHNOLOGY

DESIGN OF RIGID FRAME BRIDGE MODEL

Scale: 1" = 1'-0"


June 1932

CONCLUSIONS

CONCLUSIONS

In order to measure the deflections of the rigid frame model under load it was decided to use a level bar. This instrument consists of a spirit level set in a frame about eleven inches long. At one end of the frame is a pointed projection extending about an inch below the bar and fastened securely to it. At the other end of the bar is a micrometer screw with a pointed projection from it extending down from the micrometer. The distance between these points is ten inches. The instrument is capable of measuring a change in deflection of one-one thousandth of an inch in ten inches. The measurement of change in elevation consists of placing the two points of the level bar on the two points whose relative elevations are required, with no load on the structure, and by using the micrometer screw, bringing the level bubble exactly to the center of the glass. Then the micrometer reading may be recorded. After the load is applied, the same procedure is carried out and the difference in the micrometer readings is the change in elevation between the two points. The test model was supplied with plugs at ten inches centers along the rib for half the span, on which to rest the points of the bar. Two plugs were also placed in the footing so that the rotation there could be measured.

These plugs were placed by drilling holes and grouting them in. A sketch of the placing of these plugs is shown in Figure 12. It will be noticed that alternate plugs are center punched and the others grooved. The grooves are to provide for temperature changes




PLACING OF LEVEL BAR PLUGS

FIGURE 12

and the resultant expansion or contraction.

The arrangement of the level bar plugs gives us a means of determining the deflections at all points of the span. The readings of the level bar give us the various deflections for a number of different loadings. Following are the readings for loads of varying magnitude at different points on the span, both with ends free and with the restraining moment at the footings developed. The differences of these readings from those for no load are the deflections. The maximum deflections are the sums of all the differences of readings having a negative sign.



*Bridge Model under Construction
Vertical Legs Poured*



View Showing General Shape of Rib.

LEVEL BAR READINGS

FREE ENDS

Plugs	No Load	1500#	2000#	2500#
		at Pt. 11	at Pt. 11	at Pt. 11
1-2	.566	.596	.569	.572
3-4	.044	.039	.037	.036
4-5	.359	.354	.352	.350
5-6	.532	.526	.522	.519
6-7	.419	.411	.407	.403
7-8	.351	.343	.339	.335
8-9	.476	.471	.468	.466

Plugs	3000#	2500#	2500# at	1000# at
	at Pt. 11	at Pt. 8L	Pt. 8R	Pts. 8L, 11 and 8R
1-2	.572	.571	.569	.572
3-4	.033	.035	.040	.034
4-5	.347	.351	.355	.349
5-6	.517	-	.527	-
6-7	.399	.415	.411	.406
7-8	.332	.349	.344	.338
8-9	.464	.477	.468	.467

FREE END CONDITIONS
LEVEL BAR READINGS

DIFFERENCES IN READINGS. -Readings = Inside going down.

Load at Pt. 11

Plugs:	1500#:	2000#:	2500#:	3000#:
1-2	.003	.003	.006	.011
3-4	-.005	-.007	-.008	-.011
4-5	-.005	-.007	-.009	-.012
5-6	-.006	-.010	-.013	-.015
6-7	-.008	-.012	-.016	-.020
7-8	-.008	-.012	-.016	-.019
8-9	-.005	-.008	-.008	-.012

2500# at Pt. 8L

1-2	.003
3-4	-.004
4-5	-.004
5-6	-.005
6-7	-.008
7-8	-.007
8-9	-.008

2500# at Pt. 8R

1-2	.005
3-4	-.009
4-5	-.008
5-6	-
6-7	-.004
7-8	-.002
8-9	.001

1000# at Pts. 11, 8R and 8L

1-2	.006
3-4	-.010
4-5	-.010
5-6	-
6-7	-.013
7-8	-.013
8-9	-.009

LEVEL BAR READINGS
PARTIALLY FIXED ENDS

: Plugs	: No Load	: 1000#	: 1500#	: 2000#	:
:	:	: at Pt. 11	: at Pt. 11	: at Pt. 11	:
: 1-2	.568	.568	.568	.569	:
: 3-4	.044	.040	.040	.038	:
: 4-5	.359	.354	.354	.353	:
: 5-6	.582	.526	.525	.524	:
: 6-7	.419	.411	.412	.409	:
: 7-8	.351	.342	.343	.341	:
: 8-9	.476	.472	.472	.468	:
:					:
:					:

: Plugs	: 2500#	: 2500#	: 2500# at	: 1000# at	:
:	: at Pt. 11	: at Pt. 8L	: Pt. 8R	: Pts. 11, 8L, 8R	:
: 1-2	.571	.568	.571	.569	:
: 3-4	.037	.040	.035	.036	:
: 4-5	.350	.355	.351	.349	:
: 5-6	.519	.527	-	-	:
: 6-7	.404	.413	.416	.407	:
: 7-8	.338	.344	.349	.339	:
: 8-9	.468	.469	.477	.468	:
:					:
:					:
:					:
:					:

FIXED END CONDITIONS
LEVEL BAR READINGS
DIFFERENCES IN READINGS

Load at Pt. 11					
Plugs	1000#	1500#	2000#	2500#	
1-2	/.002	/.002	/.003	/.005	:
3-4	-.004	-.004	-.006	-.007	:
4-5	-.005	-.005	-.006	-.009	:
5-6	-.006	-.007	-.008	-.013	:
6-7	-.008	-.007	-.010	-.015	:
7-8	-.009	-.008	-.010	-.015	:
8-9	-.004	-.004	-.008	-.008	:
:					:
:					:
:					:

2500# at Pt. 8L

1-2	/.002	:
3-4	-.004	:
4-5	-.004	:
5-6	-.005	:
6-7	-.006	:
7-8	-.007	:
8-9	-.007	:
:		:
:		:

2500# at Pt. 8 R

1-2	/.005	:
3-4	-.009	:
4-5	-.008	:
5-6	-	:
6-7	-.003	:
7-8	-.002	:
8-9	/.001	:
:		:
:		:

1000# at Pts. 8L, 8R and 11.

1-2	/.003	:
3-4	-.008	:
4-5	-.010	:
5-6	-	:
6-7	-.012	:
7-8	-.012	:
8-9	-.008	:
:		:
:		:
:		:

Note: Due to position of load, no reading for plugs 5-6 were obtained in some cases.

Since we have the rotation at the footings and the changes of elevation all along the rib it becomes a fairly simple procedure to approximate the general shape of the rigid frame bridge under load. However, the assumption must be made that the detail at the knee, assumed as a right angle, does not change. This would probably not be strictly true but the error is without doubt small. The general form of the deflection curves for a few of the loadings were plotted with an exaggerated deflection scale and are reproduced here.

The deflection curves for loadings with free ends and with footings partially restrained give us an excellent opportunity to notice the effect of the restraint. Due to the moment at the footings the fixed end frame does not rotate as much at the footings and this causes less bowing out of the vertical legs and consequently less deflection in the rib. From this it is evident that the timbers under the footings are actually exerting a restraining moment.

DEFLECTION CURVE

Load at Points 8L, 11, 8R

1000*

1000*

1000*

PARTIALLY FIXED ENDS

FREE ENDS

Max Deflection - Point 11

Free Ends = .067" (Approx.)

Partially Fixed Ends = .061" (Approx.)

Deflection Scale: 1" = 2"

6L

7L

8L

9L

10L

11

10R

9R

8R

7R

6R

Points on Span

DEFLECTION CURVE

Load at Center
of Span

2500[#]

(PARTIALLY FIXED ENDS

(FREE ENDS

Max. Deflection = Point. II

Free Ends = .070"

Partially Fixed Ends = .067"

Deflection Scale: 1" = 2"

6L

7L

8L

9L

10L

II

10R

9R

8R

7R

Points on Span

6

5

4

3

2

1

DEFLECTION CURVE

Load at Point BR

2500 #

PARTIALLY FIXED ENDS

FREE ENDS

Max Deflection - Point 10R
Free Ends = .031"
Partially Fixed Ends = .034"

FREE ENDS
PARTIALLY
FIXED ENDS

Deflection Scale: 1" = .2"

6L 7L 8L 9L 10L 11 10R 9R 8R 7R 6R

Points on Span

1 2 3 4 5 6

Telemeter readings were taken for a number of different loadings at the three points on the span where the load could be applied. The seven instruments used gave readings with which the stress at almost all points on the rib and around the knee could be computed. These readings are reduced to stress by multiplying by a telemeter constant and by the modulus of elasticity of the material in which they represent the stress. The modulus of elasticity of the steel was assumed as 30,000,000 and; that of the concrete 4,000,000. This value for concrete may seem a little high but the practice among engineers who use the modulus for reduction of stress seems to be to assume it of at least that value.

The calculations to locate the neutral axis at the knee were carried out and the results indicate, as determined by other tests, that its position is very close to the inside of knee. The assumptions made in these calculations can readily be seen by inspection of the sketch accompanying the computations. By using this position of the neutral axis the actual values for the stress given by telemeter No. 7 can be obtained.


The theoretical stresses for a few of the loadings due to the live load were computed and compared with the observed stresses. These stresses seem to agree fairly well in some cases but in others they do not. It would appear that outside influences were active in a few cases, causing inaccurate readings. It might be well to state here that, due to the great sensitivity of the instruments, almost ideal conditions must be realized if exact readings are obtained. Variations of temperature are the greatest cause of this difficulty and care must be taken to protect the instruments from the sunshine.

POSITION OF NEUTRAL AXIS

Average of Readings of Telemeter #6 = $-90.4 \# / \text{sq. in.}$

Average of readings of telemeter # 7 = $254.5 \# / \text{sq. in.}$

Consider the section diagonally across knee:



$$T = \frac{8.5}{5-x} \cdot 254.5 A_s$$

$$M_o = \frac{90.4 \cdot 12x}{2} \cdot (8.5 - \frac{x}{3})$$

$$M_s = T(8.5 - \frac{x}{3}) = \frac{8.5}{5-x} \cdot 254.5 A_s (8.5 - \frac{x}{3})$$

$$M_o = 4610.4x - 180.8x^2$$

$$M_s = \frac{5840}{5-x} - \frac{229.3x}{5-x}$$

$$M_o = M_s$$

$$4610.4x - 180.8x^2 = \frac{5840}{5-x} - \frac{229.3x}{5-x}$$

$$23052x - 4610.4x^2 - 904.0x^2 / 180.8x^3 = 5840 - 229.3x$$

$$180.8x^3 - 5514.4x^2 / 23,281.3x - 5840 = 0$$

$$x^3 - 30.5x^2 / 128.8x - 32.3 = 0$$

$$\text{Solving } x = .27''$$


$$jd = 8.5 - .09 = 8.41''$$

$$j = \frac{8.41}{8.5} = .989$$


$$K = \frac{.27}{8.5} = .032$$

Readings on telemeter No. 7 must be multiplied by $\frac{8.23}{5}$ to give stress

in steel at point 6.



*View Demonstrating How Load was
Applied to Model*



*Approach Fills at Ends
of Model in place.*

Following are given the readings and corresponding stresses for some of the loadings used. The comparisons of the calculated and observed stresses for a few of the loadings are tabulated also.

CALIBRATION OF TELEMETERS

Telemeter:	Point :	Tension:	Compr.:	UNIT Strain:	Unit Stress:	Unit Strain:	Unit Stress:
No.		$\frac{f}{l}$	$\frac{f}{l}$	$\frac{f}{l}$	$\frac{f}{l}$	$\frac{f}{l}$	$\frac{f}{l}$
1	5	.000130	.000135	.000016	480.0	.000017	68.0
2	7	.000157	.000152	.000020	600.0	.000019	76.0
3	9	.000139	.000141	.000017	510.0	.000018	72.0
3	9	.000148	.000141	.000019	570.0	.000018	72.0
4	11	.000169	.000158	.000021	630.0	.000020	80.0
5	8	.000147	.000180	.000018	540.0	.000023	92.0
6	8	.000133	.000158	.000017	510.0	.000017	68.0
7	6	.000111	.00016	.000014	420.0	.000015	60.0

E_c Assumed equal to 4,000,000 in above table

E_s Assumed equal to 30,000,000

Two different instruments were used at Pt. 9 as can be seen from the above table. Some of the readings were taken one instrument and some on the other one.

OBSERVED STRESSES

LOADS AT CENTER OF SPAN

Free End Conditions

: Telemeter:		Load					:
: No.	:	: 1000#	: 1500#	: 2000#	: 2500#	: 3000#	:
: 1	Telemeter Reading	- 2.4	- 3.8	- 3.6	- 6.0	- 7.6	:
:	Stress	-163.2	- 238.0	-244.8	-408.0	-510.0	:
: 2	Telemeter Reading	- 1.7	- 4.0	- 4.2	- 6.8	- 7.0	:
:	Stress	-129.2	- 304.0	-319.2	-517.0	-532.0	:
: 3	Telemeter Reading	/ 2.0	/ 6.0	/ 12.0	/ 12.5	/ 11.6	:
:	Stress	/1020.0	/3080.0	/6120.0	/6380.0	/5910.0	:
: 4	Telemeter Reading	/ 5.0	/ 14.7	/ 8.5	/ 15.0	/ 27.4	:
:	Stress	/3150.0	/9252.0	/5355.0	/9450.0	/15618.0	:
: 5	Telemeter Reading	- 0.8	- 4.0	- 5.2	- 7.5	- 8.0	:
:	Stress	- 73.6	- 371.0	- 479.0	- 690.0	-736.0	:
: 6	Telemeter Reading	- 0.2	- 3.0	- 4.4	- 6.7	- 8.5	:
:	Stress	- 27.2	-204.0	- 299.0	- 456.0	-528.0	:
: 7	Telemeter Reading	/ 0.2	/ 8.5	/ 1.0	/ 17.2	/ 7.0	:
:	Stress	/141.0	/6000.0	/706.0	/12150.0	/4940.0	:
:							:
:							:
:							:

PARTIALLY FIXED ENDS

: Telemeter:		LOAD				:
: No.	:	: 1000#	: 1500#	: 2000#	: 2500#	:
: 1	Telemeter Reading	- 3.0	- 5.8	- 6.3	- 8.3	:
:	Stress	- 204.0	394.0	-428.0	- 564.0	:
: 2	Telemeter Reading	- 2.3	- 5.0	- 5.5	- 7.2	:
:	Stress	- 174.8	- 380.0	-418.0	-547.0	:
: 3	Telemeter Reading	/ 2.1	/ 7.3	/ 6.7	/ 12.3	:
:	Stress	/1197.0	/4160.0	/3820.0	/7010.0	:
: 4	Telemeter Reading	/ 4.3	/ 12.3	/ 8.7	/13.9	:
:	Stress	/2709.0	/7750.0	/5485.0	/8760.0	:
: 5	Telemeter Reading	- 1.4	- 4.8	- 5.5	- 7.9	:
:	Stress	- 128.8	-441.0	- 506.0	- 726.5	:
: 6	Telemeter Reading	- 1.6	- 5.7	- 4.8	- 9.2	:
:	Stress	- 108.8	-286.0	- 326.0	- 625.0	:
: 7	Telemeter Reading	/ 0.3	/ 4.2	/ 9.3	/ 17.7	:
:	Stress	/ 212.0	/2970.0	/6570.0	/12500.0	:
:						:
:						:

CALCULATED AND OBSERVED STRESSES
DUE TO LIVE LOAD

1500# at center line of span

Point	Moment	N	Arm	e	t	d	e'	e'	K
:	Inch	Pounds	M	N	Inches	t-1.5"	e/t	-1.5"	d
:	Pounds		Inches				2		Ne'
:									bd ²
5	-22680	1500	15.1	9.13	7.63	18.16	2.38		39.0
6	-27340	1379	20.0	10.00	8.50	23.50	2.76		37.4
7	-19800	443	44.7	7.50	6.00	46.95	7.82		48.1
8	-11340	443	25.6	5.75	4.25	26.98	6.35		55.2
9	-2430	443	5.5	4.75	3.25	6.38	1.96		22.2
11	-15480	443	34.9	4.25	2.75	35.63	12.95		114.0

:Point: P	:	fc	:	fs	:	Telemeter :
:	:	Pounds per sq. in.	:	Pounds per sq. inch	:	No. :
:	:	Calculated:Observ.	:	Calculated: Observed	:	:
: 5	.0038	-275	-258	7500		1 :
: 6	.0031	-270	-204	9000	/6000	6-7 :
: 7	.0044	-330	-304	10500		2 :
: 8	.0053	-360	-371	10000		5 :
: 9	.0049	-125		2800	/3060	3 :
: 11	.0160	-850		12000	/9252	4 :
:						:

line
2500# at center of span

Point	Moment	N	Arm	e	t	d	e'	e'	K
:	Inch	Pounds	M	N	Inches	t-1.5"	e/t	-1.5"	d
:	Pounds		Inches				2		Ne'
:									bd ²
5	-37800	2500	15.1	9.13	7.63	18.16	2.38		65.0
6	-45900	2292	20.0	10.00	8.50	23.50	2.76		62.4
7	-33100	739	44.7	7.50	6.00	46.95	7.82		80.2
8	-18920	739	25.6	5.75	4.25	26.98	6.35		92.1
9	-4050	739	5.5	4.75	3.25	6.38	1.96		37.0
11	-25800	739	34.9	4.25	2.75	35.63	12.95		290.0

: Point:	P	: fc	:	fs	:	Telemeter	:
:	:	: Pounds per sq. inch:	:	Pounds per sq. inch:	:	No.	:
:	:	: Calculated:	:	Observed	:	Calculated:	:
:	:	:	:	Observ.:	:	:	:
:	5	.0038	-460	-408	/12,000		1
:	6	.0031	-490	-456	/15000	/12150	6-7
:	7	.0044	-610	-517	/18,000		2
:	8	.0053	-650	-690	/17000		5
:	9	.0049	-230		/ 5,000	/ 6380	3
:	11	.0160	-1320		/13,500	/ 9450	4

OBSERVED STRESSES

1000 lbs. at Points 8L, 8R and 11.

FREE ENDS

: Telemeter	: Telemeter	: Observed	:
: No.	: Reading	: Stress	:
:	:	:	:
: 1	-4.3	-292.0	:
: 2	-5.8	-441.0	:
: 3	/0.3	/153.0	:
: 4	/14.8	/9320.0	:
: 5	-0.8	- 73.6	:
: 6	-5.3	-360.0	:
: 7	/4.8	/3330.0	:

PARTIALLY FIXED ENDS

: Telemeter	: Telemeter	: Observed	:
: No.	: Reading	: Stress	:
:	:	:	:
: 1	-5.9	-401.0	:
: 2	-2.7	-207.0	:
: 3	/5.4	/2750.0	:
: 4	/10.7	/6740.0	:
: 5	-3.7	-341.0	:
: 6	-7.2	-490.0	:
: 7	/5.8	/4015.0	:
:			:
:			:
:			:
:			:

OBSERVED STRESSES
FREE ENDS

2500 lbs. at Pt. 8R

Telemeter	Telemeter	Stress
No.	Reading	
1	-3.0	-204.0
2	-1.0	-76.0
3	/4.2	/2142.0
4	/2.0	/1260.0
5	-1.2	- 110.4
6	-	-
7	-	-

2500 lbs. at Pt. 8L

Telemeter	Telemeter	
No.	Reading	Stress
1	-2.0	-136.0
2	-3.6	-273.6
3	/8.0	/4080.0
4	/2.0	/1260.0
5	/6.7	/3610.0
6	-1.6	-108.8
7	/2.0	/1410.0

PARTIALLY FIXED ENDS

2500 lbs. at Pt. 8R

Telemeter	Telemeter	
No.	Reading	Stress
1	-3.8	-258.0
2	-1.3	- 98.8
3	/3.7	/2110.0
4	/2.8	/1765.0
5	-0.2	- 18.4
6	-0.2	- 13.6
7	/0.5	/345.0

2500 lbs. at Pt. 8L

Telemeter	Telemeter	
No.	Reading	Stress
1	-0.9	-61.2
2	-4.2	- 319.0
3	/0.9	/ 513.0
4	/1.7	/1070.0
5	/7.6	/ 411.0
6	-4.3	- 292.0
7	/8.7	/6020.0

CALCULATED AND OBSERVED STRESSES
DUE TO LIVE LOAD

2500# at Pt. 8 R

Point	Moment	Arm						K
	Inch-	N	M/N	t	d	e/t-1.5"	e'	No'
	Pounds	Pounds	Inches	Inches	=t-1.5"	$\frac{e}{t}$	$\frac{e'}{d}$	$\frac{No'}{bd^2}$
5R	-20,850	2500	8.35	9.13	7.63	11.41	1.50	40.9
6R	-25,500	2060	12.37	10.00	8.50	15.87	1.87	37.8
7R	- 2,400	400	6.00	7.50	6.00	8.25	1.37	7.6
8R	/21,300	400	53.25	5.75	4.25	54.63	12.87	100.8
9R	/15,000	400	37.50	4.75	3.25	38.38	11.80	121.0
11	/ 2,700	400	6.75	4.25	2.75	7.38	2.68	32.5
9L	- 9,000	400	22.50	4.75	3.25	23.38	7.19	73.8
8L	-14,850	400	37.13	5.75	4.25	38.51	9.06	71.0
7L	-20,600	400	51.50	7.50	6.00	53.75	8.96	49.7
6L	-25,500	2060	12.37	10.00	8.50	15.87	1.87	37.8
5L	-20,850	2500	8.35	9.13	7.63	11.41	1.50	40.9

Point	P	fc		fs		Telemeter
		Pounds per sq. inch		Pounds per sq. Inch		
		Calculated	Observed	Calculated	Observed	No.
5R	.0038	-250	-204	/5000		1
6R	.0031	-280	-108.8	/7500	/1410	6-7
7R	.0044	- 50	- 76	/1000		2
8R	.0053	-750		/12000	/3610	5
9R	.0049	-900		/22000	/2142	3
11	.0060	-150		/1500	/1260	4
9L	.0049	-540		/14500	/4080	3
8L	.0053	-500	-110.4	/13000		5
7L	.0044	-420	-273.6	/12300		2
6L	.0031	-280		/7500		6-7
5L	.0038	-250	-136	/5300		1

The results of the tests indicated that the restraint caused by the timbers is of an appreciable amount and should be provided for in the design. The practice of using an intermediate design between the free end case and the fixed end case, when piles are used would seem to be safe. The telemeter readings for the case with partially fixed ends were greater in the region of the knee and less at the center of the span indicating a greater negative moment and a smaller positive moment, although the variations of the strain gage readings fail to evaluate these differences for us. The differences of deflections for the two cases would indicate the same conditions.

The calculated stresses were, in almost every case, of greater values than the corresponding observed stresses. This fact might be explained by the action of the earth fills at the ends of the bridge. Although no exact value can be assigned to this pressure, it is evident that a passive earth pressure must be developed by these fills. When the vertical legs deflect outward the action of the earth in resisting this movement is equivalent to an active pressure on the frame. From the amount of the differences in the calculated and observed stresses the amount of this passive pressure would seem to be quite large. This, of course, is on the assumption that the earth pressure accounts for all of the difference, which fact may not be entirely true.

An attempt was made to load the model to destruction but, with the available equipment, sufficient load could not be applied to cause a failure. A load of 6000 lbs. was applied at the center of the span, but due to the large deflection in the timbers under the

bridge the range of the jack type lodometer prevented the addition of more load. Under the load of 6000 lbs. hair cracks over the tension reinforcement could be discerned at the center of the span.

The rigid frame bridge model demonstrated to the writer a remarkable strength and rigidity, considering the slender proportions of the structure. The economies effected by the rigid frame bridge are easily seen. When we couple that important fact with the consideration of its grace and symmetry, there can be small wonder that it is rapidly gaining popularity as one of the finest types of short span bridges.